



Climate changes in the central Mediterranean and Italian vegetation dynamics since the Pliocene



Nathalie Combourieu-Nebout ^{a,b,*}, Adèle Bertini ^c, Elda Russo-Ermolli ^{a,d}, Odile Peyron ^{e,f}, Stefan Klotz ^g, Vincent Montade ^{e,f,h}, Severine Fauquette ^f, Judy Allen ⁱ, Fabio Fusco ^j, Simon Goring ^k, Brian Huntley ⁱ, Sébastien Joannin ^{e,f,l}, Vincent Lebreton ^a, Donatella Magri ^m, Edoardo Martinetto ⁿ, Ronan Orain ^a, Laura Sadori ^m

^a HPNP, UMR 7194 CNRS, Département de Préhistoire du Muséum national d'Histoire naturelle, 1 rue René Panhard, F-75013 Paris, France

^b LSCE, UMR 8212 CNRS/UVSQ/CEA, Orme des merisiers, F-91198 Gif sur Yvette, France

^c Dipartimento di Scienze della Terra, Università di Firenze, via G. La Pira 4, 50121 Firenze, Italy

^d Dipartimento di Scienze della Terra, dell'Ambiente e delle Risorse, Università di Napoli Federico II, Largo San Marcellino 10, 80138 Napoli, Italy

^e CBAE, UMR 5059 CNRS/EPHE/UM2/INRAP, Institut de Botanique, 163 rue A. Broussonet, 34090 Montpellier, France

^f ISEM, UMR 5554 CNRS, Université Montpellier 2, Place Eugène Bataillon, 34095 Montpellier cedex 05, France

^g Geographisches Institut, Universität Tübingen, Rümelinstr. 19–23, 72070 Tübingen, Germany

^h Ecole Pratique des Hautes Etudes, EPHE, 4–14 rue Ferrus, 75014 Paris, France

ⁱ School of Biological and Biomedical Sciences, Durham University, South Road, Durham DH1 3LE, UK

^j LIPPIA, Laboratorio Indipendente di Palinologia Paleontologica, Investigativa ed Ambientale, Viale G. Bovio 10, 65123 Pescara, Italy

^k Department of Geography, University of Wisconsin–Madison, WI 53706, USA

^l LGL TPE, UMR 5276 CNRS, Université de Lyon1, 2 rue Dubois, 69622 Villeurbanne Cedex, France

^m Dipartimento di Biologia Ambientale, Sapienza Università di Roma, P. le Aldo Moro 5, Roma, Italy

ⁿ Dipartimento di Scienze della Terra Università degli Studi di Torino, Via Valperga Caluso 35, 10125 Torino, Italy

ARTICLE INFO

Article history:

Received 6 May 2014

Received in revised form 20 January 2015

Accepted 1 March 2015

Available online 11 March 2015

Keywords:

Central Mediterranean

Vegetation

Climate

Pliocene

Quaternary

Palynology

ABSTRACT

Pollen records and pollen-based climate reconstructions from the Italian peninsula (central Mediterranean) show clear signals of vegetation change linked to variations in water availability in the Mediterranean basin over the past 5 million years. Profound vegetation changes occurred in four major steps from the Pliocene to the present. The subtropical taxa that dominate Pliocene assemblages declined and then disappeared between 3–2.8 and 1.66 Ma (at around 2.8 Ma in the North and later in the South), progressively being replaced by temperate *Quercus* forests at mid altitude. In the south Italy, *Quercus* expanded more at around 1.4–1.3 Ma and *Fagus* proportions increased after 0.5 Ma. Conifer forest (first mainly composed of *Tsuga* then by *Abies* and *Picea*) began to expand at 2.8 Ma, probably rather at high altitude, beginning at 2.8 Ma. Mediterranean-type forest, rare during the Early Pleistocene, developed and increased in diversity during the Middle Pleistocene. Open landscapes, with higher abundances of steppic taxa, became more frequent and extensive at the onset of Glacial/Interglacial (G/I) cyclicity around 2.6 Ma and gradually expanded with more and more marked glacials. Climate reconstructions done on selected pollen records from southern Italy suggest a decline in winter temperature and annual precipitation from the early Pleistocene to the Holocene. Specifically, both precipitation and winter temperature reconstructions show changes in interglacial maxima and glacial minima at around 3–2.8 Ma, 2 Ma, 1.3–1.4 Ma and 0.5 Ma. This critical review provides evidence that the North–South precipitation gradient, with drier conditions in the South, has been a consistent feature of the Italian peninsula since the beginning of the Pleistocene.

© 2015 Elsevier B.V. All rights reserved.

1. Introduction

The Mediterranean basin is considered a global biodiversity hotspot (e.g. Médail and Quézel, 1997, 1999; Giorgi, 2006; Christensen et al.,

2007). Given projections of future regional climate change, growing demographic pressures in coastal zones, and the particular importance of water resources in the region, the preservation of ecosystems within the basin is considered a key goal for governments (IPCC, 2007). Water availability is a key factor limiting plant growth and is an important driver of vegetation composition (Daget, 1977; Venetier et al., 2010). The future composition of Mediterranean ecosystems is thus clearly tied to water availability. While modern vegetation data from the region provide a baseline for understanding relationships between aridity and vegetation composition, paleoecological records provide support for

* Corresponding author at: UMR 7194 CNRS "Histoire Naturelle de l'Homme Préhistorique" Département de Préhistoire, Muséum national d'histoire naturelle Institut de Paléontologie Humaine 1, rue René Panhard, F-75013 Paris, France. Tel.: +33 1 55 43 27 55; fax: +33 1 43 31 22 79.

E-mail address: nneboutcomboureu@mnhn.fr (N. Combourieu-Nebout).

understanding vegetation responses at longer time scales (e.g. Bertini, 2010; Joannin et al., 2012; Combourieu-Nebout et al., 2013; Peyron et al., 2013 and references therein). Paleocological records show that aridity, as a feature of the Mediterranean basin, appeared recently, gradually increasing up to the present time (Pons et al., 1995). Even during the Messinian salinity crisis (MSC, 5.9–5.3 Ma), aridity did not play a major role in restructuring vegetation (Suc and Bessaïs, 1990; Bertini, 2006; Fauquette et al., 2006 and references therein). What we now call Mediterranean-type taxa have been present in the basin since the Paleocene, but only sporadically until they increased in importance during the last several thousand years. The development of modern Mediterranean ecosystems seems to be linked to increasing dryness and seasonality, with increasingly dry summers focusing moisture deficiency during the summer months (Pons et al., 1995; Quézel and Médail, 2003).

Researchers have documented a stepwise Pliocene–Pleistocene development of modern Mediterranean ecosystems and climate, although the rarity of records has hindered basin-wide reconstructions (Pons et al., 1995; Sadori et al., 2013a). Given the limited number of Mediterranean available records, reconstructing long-term (5 Myr) vegetation changes on the Italian peninsula will help to identify links between vegetation changes and increasing aridity in the region. The Italian peninsula stretches across the centre of the north Mediterranean basin, running in a northwest to southeast direction. The Apennine Chain forms the backbone of the peninsula, and within the peninsula generate heterogeneous environmental conditions that support vegetation that varies with elevation and latitude. Several distinct climatic systems influence the Italian climate: polar air masses from the North; tropical air masses from the South; Atlantic Westerlies; and a monsoon system from the East (Lionello et al., 2006). This results in a climate gradient from north to south with a mosaic of local/regional situations, with usually higher humidity in the north and increasing aridity to the south. Italy thus represents one of the most informative Mediterranean areas to: (i) reconstruct the response of vegetation to various climatic stresses; and (ii) assess the likely future behaviour of Mediterranean plants. Furthermore, the Italy's rich geological and stratigraphical record makes it a significant source of information on the history of Mediterranean vegetation.

In this paper we describe vegetation reconstructions grouped in two areas: Northern and Southern Italy, placing the boundary between the two at 42.5°N. This latitude approximately splits the Italian peninsula according to the present duration of the dry season between areas to the south where this exceeds three months and those to the north where it is shorter. This division allows us to describe continuous long- and short-term climate and vegetation changes in the Mediterranean basin during the last 5 million years.

2. Present day Italian climate and vegetation

Italy is a mountainous country, bounded in the North by the Alps, and with the Apennines running as a backbone from northwest to southeast.

Located at mid-latitude (47°N to 37°N) and towards the western margin of the Eurasian landmass, the Italian peninsula exhibits a classic Mediterranean climate, with mild winters (especially in the hilly and coastal areas) and pronounced summer drought (Fig. 1). The influence of the Mediterranean climate on vegetation is most evident at lower altitudes and on the coasts, becoming attenuated with increasing altitude on the pre-Alpine chains and in the Apennines. In the Apennines, summers are cooler and moister with increasing altitude, whereas continentality increases towards and into the Alpine mountains, leading to increased annual temperature range, with colder winters and summers that are hot but not markedly dry. The Po Valley, a large plain situated in the north between the western Ligurian Alps and the Adriatic Sea, is relatively continental in climate. This is principally due to its proximity to the Alps and its separation from the Mediterranean proper by the Apennines. The Italian peninsula thus spans a clear and complex

gradient from the southern warm-temperate Mediterranean climate, through the cool-temperate climate of the Apennines and pre-Alpine ranges, to the continental climate of the innermost Alps with its strong temperature seasonality. This complex topographic and climatic landscape has deeply affected the flora of the peninsula. The Italian vegetation is well documented (e.g. Tomaselli et al., 1973; Ozenda, 1975; Bonin, 1981; Ozenda, 1994; Pignatti, 1998; Quézel and Médail, 2003; Blasi, 2010). The European potential natural vegetation zones and the main physiognomic–ecological units for the Italian peninsula are summarised in Fig. 1 (modified from Pignatti, 2011).

3. Materials and methods

3.1. Pollen records

We use vegetation reconstructions based on palynology and paleobotanical information available from the Italian peninsula (Fig. 2, Table 1). These data help to reconstruct vegetation changes in Italy, and their links to increasing aridity since the Pliocene. The pollen records presented here are distributed unevenly across the region, and so each site has been assigned to either “Northern” or “Southern” Italy relative to latitude 42.5°N, the isocline for current dry season duration (longer or shorter than 3 months) (Figs. 1 and 2). Vegetation types inferred from pollen records and the literature are plotted for glacial and interglacial within six key geological intervals during the last 5 Myr: Pliocene (Zanclean, 5.332–3.600 Ma, and Piacenzian, 3.600–2.588 Ma); Early Pleistocene (Gelasian, 2.588–1.806 Ma, and Calabrian, 1.806–0.781 Ma); Middle Pleistocene (“Ionian”, 0.781–0.126 Ma); Late Pleistocene (“Tarantian”, 0.126–0.01 Ma); and Holocene (last 0.01 Ma) (Fig. 3a and b). Sixteen sites that combine long time series, coverage for key time intervals and consistent age models (Table 1 and Fig. 2 in red), provide the opportunity to develop a model of continuous vegetation change throughout Italy. Pollen diagrams for these sites have been plotted using Psimpoll (Bennett, 2008) for a subset of taxa selected to illustrate the major changes in Italian vegetation since the Pliocene (Fig. 4a and b).

The taxon “Taxodiaceae” is referred to in quotation marks throughout because many genera formerly assigned to this family are now placed in subfamilies of Cupressaceae, for example, Taxodioideae Endl. ex K. Koch (*Taxodium*, *Glyptostrobus* and *Cryptomeria*) and Sequoiioideae (Luerss.) Quinn (*Sequoia*, *Sequoiadendron* and *Metasequoia*). The genus *Sciadopitys* is now generally placed in Sciadopityaceae (Brunsfield et al., 1994; Farjon, 1998, 2005). However, the term “Taxodiaceae” has been commonly used in Italian records where it is generally assumed to represent *Sciadopitys*, *Taxodium* type (which includes *Taxodium* cf. *distichum* and *Glyptostrobus*) and *Sequoia* type (which includes *Cryptomeria*, *Cunninghamia*, *Metasequoia glyptostroboides*, *Sequoiadendron giganteum* and *Sequoia sempervirens*). Because of the ecological diversity of taxa represented by the term “Taxodiaceae” it is difficult to revisit the records and apply the new taxonomy; we have therefore chosen to keep the term “Taxodiaceae”, as used in older publications, although providing greater clarity where possible.

3.2. Climate reconstructions

Climate reconstructions from pollen records allow us to understand the climate trends that have driven changes in Italian vegetation over the last 5 Ma. Depending on the period of interest we have used different methods for reconstructing climate. Annual precipitation and temperature have been reconstructed using: (1) probability mutual climatic spheres (PCS); and (2) the Modern Analogue Technique (MAT). The PCS method uses the modern climatic requirements of plant taxa, transposed to plant assemblages (Klotz, 1999; Klotz et al., 2006) and has been applied using 60 of the 110 taxa identified in fossil pollen floras from the Pliocene to Early Pleistocene (e.g. Fauquette et al., 1999; Klotz et al., 2006; Fauquette et al., 2007). The PCS method is




Fig. 1. Present-day vegetation and climate in Italy (modified from Pignatti, 2011). A selection of climate (ombrothermic) diagrams (calculated using the NewLocClim software, Grieser et al., 2006) illustrates the modern north–south climate gradient.

considered the best way to reconstruct climate parameters from geologically older pollen records representing vegetation associations including exotic or subtropical taxa and thus lacking a modern analogue. Mean temperature of the coldest month (MTCO) and mean annual precipitation (PANN) are presented here for PCS reconstructions performed on the older records. The MAT has been successfully applied to several Middle Pleistocene to Holocene records to produce pollen-based reconstructions of climate variables (e.g. Guiot, 1990; Joannin et al., 2011; Combourieu-Nebout et al., 2013; Peyron et al., 2013). The vegetation

associations recorded in pollen diagrams for these intervals are compared to a collection of surface samples (database of >3000 surface pollen spectra from Europe and Mediterranean area) with their associated biomes and climate variables from various origin to reconstruct past climate variables (for details see Peyron et al., 1998, 2011, 2013). Mean temperature of the coldest month (MTCO), mean summer (June–July–August) precipitation (PSUM), mean winter (December–January–February) precipitation (PWIN) and mean annual precipitation (PANN) are presented here for MAT reconstructions.




Fig. 2. Selected Italian sites: 1) Azzano Decimo; 2) Lago di Ledro; 3) Piànico-Sèllere, Lefte, Fornaci di Ranica; 4) Fimon; 5) Venice; 6) Pianengo; 7) Rio Ca' Viettone; 8) Villafranca RDB; 9) Stirone, Castell'Arquato (Campile), Monte Falcone-Rio Crevaiese; 10) Compiano; 11) Aulla-Vallescura; 12) Monticino 1987, Lamone composite section; 13) Core S8 and core S13 (Po plain); 14) Sarzana; 15) Cava di Villanova; 16) Castel d'Appio; 17) Val Marecchia; 18) Lower Valdarno basin: San Quintino, Ponte a Elsa and other sections; 19) Upper Valdarno basin: Santa Barbara, Rena Bianca and other composite sections; 20) Maccarone; 21) Gubbio; 22) Lago dell'Accesa; 23) Pietrafitta, Tiberino basin: Fosso Bianco, Cava Toppetti and other composite sections; 24) Colle Curti-Cesi composite section; 25) Leonessa; 26) Lagaccione, Lago di Vico; 27) Marine core RF93-30; 28) Madonna della Strada; 29) Corvaro, Borgorose and Marano de' Marsi; 30) Valle di Castiglione, Valle Ricca; 31) Fontana Ranuccio; 32) Lago Battaglia; 33) Sessano, La Pineta-Isernia; 34) Boiano; 35) Marine core MD 90-917, Marine core AD 91-17, Marine core KET 82-16, Marine core KET SA 03-1, Marine core IN 68-9; 36) Saticula (Sant'Agata de' Goti – BN); 37) Acerno; 38) Monticchio; 39) Salerno marine core C106; 40) Vallo di Diano; 41) Montalbano Jonico, Sant'Arcangelo; 42) Lago Alimini; 43) Camerota; 44) Mercure; 45) Lago di Trifoglietti; 46) core KET8003; 47) Valle di Manche; 48) Semaforo and Vrica sections, Santa Lucia; 49) Bianco; 50) Monte Singa; 51) Canolo Nuovo; 52) Le Castella; 53) Lago di Preola; 54) Lago di Pergusa; 55) Punta Piccola, Capo Rossello composite section; 56) Monte San Giorgio; 57) Monte San Nicola (Gela); 58) marine core MD 01-2797. Sites used for pollen diagrams (Figs. 3 and 8) and pollen based climate reconstructions (Fig. 7) are indicated in red. The orange dotted line represents the 42.5°N latitudinal limit between Northern and Southern Italy.

Our synthesis represents the first compilation of climate reconstructions from this region to span the entire Pleistocene, a time of major vegetation changes, and the first to separate cold and warm intervals during the Middle and Late Pleistocene. Because the temporal resolution is generally poor, reconstructed climate is presented as box-and-whisker plots for temperature and/or precipitation within the chosen intervals. For MTCO, PWIN, PSUM and TANN, separate plots were calculated for glacial and interglacials. Box-and-whisker plots were made using R software, the boxes representing the extent of the second and third quartiles, and the dotted delimited whisker lines representing extreme values. The median is indicated by a heavy line within the box.

3.3. Chronology

Published age models provided the chronologies used for the pollen records. Age models for the most recent time intervals were based on ^{14}C dates, links to Greenland ice-core records and tephra layer data,

whereas for the geologically older records K/Ar dates, biostratigraphy (foraminifers and nanofossils), links to oxygen isotope records from Mediterranean or Atlantic marine sediment cores and astronomical tuning were variously used. It is not part of our review to discuss the individual age models, although we acknowledge that each has its own limitations. Instead, our aim is to reconstruct the general pattern of Italian vegetation changes from the Pliocene to the present day.

4. Italian vegetation and a trend towards increasing drought

4.1. Emergence of Mediterranean vegetation communities in Italy

Climate in the Mediterranean has changed repeatedly since the tropical, warm-humid conditions of the Eocene. The development of the Mediterranean climate regime, punctuated by a dry summer season, occurred in the late Pliocene (Suc, 1984), a time when cooling is observed in marine records (Poore and Berggren, 1975; Sprovieri et al., 2006).

Table 1

List of the sites used in this paper with their location, sediment type (P/L, peatbog and lacustrine sequences; T, other continental sequences; M, marine cores), the time interval covered and the main related bibliographic references (bold text indicates those with the site palynology included; italic text indicates other relevant references).

n.	Sites	Lat N	Long E	Alt./depth	Locality	C/L	T	M	Age Interval	References *
1	Azzano Decimo	45°53'20"N	12°42'50"E	14 m asl	Friuli				Last 215 ka	Pini et al., 2009a
2	Lago di Ledro	45°51'46"N	10°44'46"E	860 m asl	Trentino				Holocene	Joannin et al., 2013
3	Pianico-Sellere	45°51'06"N	10°03'35"E	1080 m asl	Lombardy				Controversial age: 1. Riss-Wurm Interglacial, 2. 779 ± 13 ka, 3. ca 400 ka (MIS 11)	Moscariello et al., 2000; Rossi, 2003; de Beaulieu et al., 2006; Pinti et al., 2001; Rouleau et al., 2009, Brauer et al., 2007a, 2008
3	Lefte	45°53'13"N	9°52'09"E	950 m asl	Lombardy				Okluvai (1.94–1.78 Ma) up to 0.87 Ma	Lona, 1950; Lona and Follieri, 1957; Lona and Bertoldi, 1972; Ravazzi, 1993, 2003; Ravazzi and Rossignol-Strick, 1994; 1995; Ravazzi and Moscariello, 1998; Muttoni et al., 2007, Ravazzi et al., 2009; Cremaschi and Ravazzi, 1995; Martinetto, 2009
3	Fornaci di Ranica	45°45'07"N	9°42'55"E	500 m asl	Lombardy				Late Calabrian	Ravazzi et al., 2005
4	Fimon	45°30'22"N	11°31'45"E	41 m asl	Veneto				Last 130 ka	Pini et al., 2009b
5	Venice	45°27'44"N	12°18'35"E	0 m asl	Veneto				Quaternary	Mullenders et al., 1996; Kent et al., 2002; Canali et al., 2007; Massari et al., 2004
6	Pianengo	45°25'43"N	9°41'34"E	142 m slm	Lombardy				Late Matuyama to the early Brunhes	Muttoni et al., 2003
7	Rio Ca' Viettone	45°12'N	7°35'E	N/A	Piedmont				Pliocene (? Most probably Late Zanclean)	Allason et al., 1981; Bertoldi and Martinetto, 1995
8	Villafranca RDB	44°48'46"N	7°29'38"E	380 m asl	Piedmont				Zanclean-Piacenzian	FrancaVilla et al., 1970; Lona and Bertoldi, 1972; Carraro et al., 1996; Martinetto and Vassio, 2010
9	Stirone	44°50'N	9°58'E	140 m asl	Emilia-Romagna				Zanclean to Calabrian	Lona and Bertoldi, 1972; Becker-Platen et al., 1977; Bertolani-Marchetti et al., 1979; Bertini, 1994, 2001; Fauquette and Bertini, 2003; Mai, 1995; Martinetto et al., 2007
9	Castell'Arquato (Campile)	44°51'13"N	9°52'14"E	224 m asl	Emilia-Romagna				Gelasian	Lona, 1962; Lona and Bertoldi, 1972; Mai, 1994; Martinetto et al., 2015
9	Monte Falcone-Rio Crevalse	44°51'13"N	9°52'14"E	N/A	Emilia-Romagna				Late Piacenzian	Monegatti et al., 1997, 2002
10	Compiano	44°33'34"N	9°39'09"E	332 asl	Emilia-Romagna				Early Pleistocene (?)	Bertoldi, 1985b; Martinetto et al., 2015
11	Aulla-Vallescura	44°14'13"N	9°47'57"E	547 m asl	Tuscany				Pliocene (Zanclean or Piacenzian?)	Bertoldi, 1988; Bertoldi and Castello, 1990
12	Monticino 1987	44°23'53"N	11°34'20"E	148 m asl	Emilia-Romagna				Late Messinian to Zanclean	Bertini, 1994, 2006; Vai, 1988 and references therein
12	Lamone composite section	44°18'35"N	11°54'41"E	26 m asl	Emilia-Romagna				Calabrian, MIS 64 to MIS 46	Fusco, 1996, 2007, 2010; Vaiani and Venezia, 1999
13	Po Valley : core 240-S8	44°18'35"N	12°E	N/A	Emilia-Romagna				Holocene	Amorosi et al., 2004; Cibi et al., 2005
13	Po Valley : core 240-S13	44°18'35"N	12°E	N/A	Emilia-Romagna				Late Pleistocene to Holocene	Amorosi et al., 2004
14	Sarzana	44°08'20"N	9°57'30"E	298 m asl	Liguria				Pliocene (Zanclean or Piacenzian?)	Bertoldi et al., 1994; Federici, 1973
15	Cava di Villanova	44°02'27"N	8°06'09"E	194 m asl	Liguria				Zanclean	Zheng, 1990; Zheng and Cravatte, 1986 and references therein
16	Castel d'Appio	43°48'12"N	7°34'31"E	287 m asl	Liguria				Zanclean	Zheng, 1990; Zheng and Cravatte, 1986 and references therein
17	Val Marecchia	43°58'39"N	12°18'08"E	300 m asl	Emilia-Romagna				Piacenzian-Gelasian	Rio et al., 1997
18	Lower Valdarno basin: San Quintino, Ponte a Elsa and other sections	43°41'15"N	10°53'55"E	60 m asl	Tuscany				Piacenzian-Gelasian	Valleri et al., 1990; Benvenuti et al., 2007; Bossio et al., 1993; Benvenuti and Degli Innocenti, 2001; Martinetto et al., 2015
19	Upper Valdarno basin: Santa Barbara, Rena Bianca and other composite sections	43°33'47"N	11°28'33"E	143 m	Tuscany				Gelasian to Calabrian	Follieri, 1977; Albani et al., 1995; Bertini and Roiron, 1997; Bertini, 2002, 2003, 2010, 2013; Napoleone et al., 2003; Ghinassi et al., 2004; Mai, 1994
20	Maccarone	43°25'31"N	13°06'55"E	225 m asl	Marche				Late Messinian to Zanclean	Bertini, 1994, 2006; Carloni et al., 1974
21	Gubbio	43°22'40"N	12°33'56"E	358 m asl	Umbria				Pleistocene	Lona and Ricciardi, 1961a; Ricciardi, 1965; Fusco, 2010
22	Lago dell'Accesa	42°59'19"N	10°53'37"E	260 m asl	Tuscany				Holocene	Drescher-Schneider et al., 2007
22	Pietrafitta	43°01'17"N	12°12'36"E	318 m asl	Umbria				MIS 58 to MIS 28	Ricciardi, 1961; Ge.Mi.Na, 1962; Lona and Bertoldi, 1972; Fusco, 2010
23	Colle Curti - Cesi composite section	43°01'N	12°53'E	850 m, 820 m asl	Umbria					Bertini, 2000; Ficcarelli et al., 1997; Coltorti et al., 1998
24	Tiberino basin: Fosso Bianco, Cava Toppetti and other composite sections	42°36'N	12°30'57"E	187 m asl	Umbria-Marchean Apennines				Upper Early to lower Middle Pleistocene	Pontini, 1997; Pontini and Bertini, 2000; Pontini et al., 2002; Basilici, 1997; Martinetto et al., 2014
25	Leonessa	42°35'11"N	12°57'37"E	930 m asl	Rieti				MIS 62 (?) to MIS 28, according to Fusco (2010)	Ge. Mi.Na., 1962; Ricciardi, 1965

in red, pollen data included in this paper

wd: water depth N/A not found
asl: above sea level

* References including palynology are in bold;
other references in italic

(continued on next page)

n.	Sites	Lat N	Long E	Alt./depth	Locality	C/L	T	M	Age Interval	References *
25	Lagaccione	42°34'N	11°51'E	355 m asl	Latium				Last 130 ka	Magri, 1999; Narcisi and Anselmi, 1998
26	Lago di Vico	42°20'18"N	12°09'56"E	557 m asl	Latium				Last 90 ka	Leroy et al., 1996; Magri and Sadori, 1999
27	Marine core RF 93-30	42°40'01"N	15°40'03"E	77 m wd	central Adriatic Sea				Holocene	Oldfield et al., 2003; Piva et al., 2008
28	Madonna della Strada	42°20'55"N	13°15'16"E	1590 m asl	Abruzzi				Calabrian	Magri et al., 2010
29	Corvaro	41°12'36"N	13°13'55"E	1074 m asl	Latium				Middle-Late Pleistocene	Chiarini et al., 2007
29	Borgorose and Marano de' Marsi	42°08'56"N	13°15'59"E	720 m asl	Latium				Early Pleistocene	Sadori et al., 2010; Chiarini et al., 2007, 2009
30	Valle di Castiglione	42°N	12°E	44 m asl	Latium				Last 250 ka	Follieri et al., 1988; Di Rita et al., 2013; Narcisi et al., 1992
30	Valle Ricca	42°N	12°E	50 m asl	Latium				Early Pleistocene	Urban et al., 1983; Arias et al., 1990; Borzi et al., 1998; di Bella et al., 2005
31	Fontana Ranuccio	41°53'33"N	13°06'13"E	235 m asl	Latium				Early Pleistocene	Corrado and Magri, 2011
32	Lago Battaglia	41°53'N	16°10'E	20 m asl	Apulia				Late Holocene	Caroli and Caldara, 2007
33	Sessano	41°38'44"N	14°19'51"E	700 m asl	Molise				MIS 15 to MIS 12	Russo Ermolli et al., 2010a; Amato et al., 2011
33	La Pineta-Isernia	41°37'06"N	14°13'34"E	450 m asl	Molise				~700-800 ka	Lebreton, 2002; van Otterloo and Sevink, 1983; Cremaschi, 1983; Cremaschi and Peretto, 1988; Delitala et al., 1983; von Koenigswald and Kolfschote, 1996; Belluomini et al., 1997
34	Boiano	41°29'46"N	14°28'11"E	660 m asl	Molise				Middle Pleistocene	Orain et al., 2013 and reference therein; Aucelli et al., 2011
35	Marine core MD 90-917	41°17'N	17°37'E	1010 m wd	south Adriatic Sea				Last deglaciation and Holocene	Combourieu-Nebout et al., 1998, 2013
35	Marine core AD 91-17	40°52'17"N	18°38'15"E	845 m wd	south Adriatic Sea				Holocene	Sangiorgi et al., 2003; Giunta et al., 2003
35	Marine core KET 82-16	41°31'N	17°59'E	1166 m wd	south Adriatic Sea				Last deglaciation and Holocene	Rossignol-Stick et al., 1992
35	Marine core KET SA 03-1	41°30'25"N	17°10'77"E	567 m wd	south Adriatic Sea				Last deglaciation and Holocene	Favaretto et al., 2008
35	Marine core IN 68-9	41°47'5"N	17°54'5"E	609 m wd	south Adriatic Sea				Last deglaciation and Holocene	Zonneveld, 1996
36	Saticula (Sant'Agata de' Goti - BN)	41°06'14"N	14°30'10"E	200 m asl	Campania				late Early Pleistocene	Russo Ermolli et al., 2010b
37	Acerno	40°49'50"N	15°02'44"E	650 m asl	Campania				MIS14 to MIS12	Russo Ermolli, 2000; Munno et al., 2001; Petrosino et al., 2014a
38	Monticchio	40°56'N	15°35'E	681 m asl	Basilicata				Last 127 ka	Watts et al., 1996, 2000; Allen and Huntley, 2000, 2009; Brauer et al., 2000, 2007b
39	Salerno marine core C106	40°28'22"N	14°42'24"E	292 m asl	South Tyrrhenian Sea				Last 30 ka	Russo Ermolli and Di Pasquale, 2002; Di Donato et al., 2008; Bucchieri et al., 2002
40	Vallo di Diano	40°16'17"N	15°37'06"E	450 m asl	Campania				650 to ca 450 Ka (MIS 16 to 13) (Karner et al., 1999)	Russo Ermolli, 1994; Russo Ermolli et al., 1995; Russo Ermolli and Cheddadi, 1997
41	Montalbano Jonico	40°17'N	16°34'E	226m asl	Basilicata				1.240 to 0.900 Ma (MIS 37 to 23)	Joannin et al., 2008
41	Sant'Arcangelo	40°15'51"N	16°16'30"E	236 m asl	Basilicata				Jaramillo subchron to Brunhes chron	Sabato et al., 2005
42	Lago Alimini	40°11'27"N	18°26'34"E	35 m asl	Apulia				Late Holocene	Di Rita and Magri, 2009
43	Camerota	40°02'33"N	15°22'30"E	300 m asl	Campania				Early Pleistocene	Baggioni et al., 1981; Brenac, 1984; Russo Ermolli, 1999
44	Mercure	39°58'07"N	16°02'04"E	300 m asl	Basilicata /Calabria				Middle Pleistocene	Lona and Ricciardi, 1961b; Petrosino et al., 2014b; Robustelli et al., 2014
45	Lago di Trifoglietti	39°32'34"N	16°00'14"E	400 m asl	Calabria				Holocene	Joannin et al., 2012
46	core KET8003	38°49'N	14°29'E	1900 m wd	South Tyrrhenian Sea				Tarantian-Holocene	Rossignol-Stick et al., 1989
47	Valle di Manche	39°05'35"N	16°55'14" E	205 m	Calabria				MIS 22 to MIS 18.3	Capraro et al., 2005; Massari et al., 2002
48	Semaforo and Vrica sections	39°N	16°42'E	50 m asl	Calabria				Semaforo (2.46 to 2.11 Ma) and Vrica (2.2-1.36 Ma)	Combourieu-Nebout et al., 1990, 2000; Combourieu-Nebout and Vergnaud-Grazzini, 1991; Combourieu-Nebout, 1993; 1995; Klotz et al., 2006
48	Santa Lucia	39°N	16°42'E	161 m asl	Calabria				Late Early Pleistocene	Joannin et al., 2007; Lourens et al., 1996
49	Bianco	38°04'25"N	16°08'21"E	61 m asl	Calabria				Pliocene (ca 3.7-3 Ma)	Bertoldi et al., 1989; Howell et al., 1988; Rio et al., 1989
50	Monte Singa	38°10'N	16°08'18"E	61 m asl	Calabria				Early Pleistocene (2.5-2.45 Ma)	Combourieu-Nebout et al., this paper; Lourens et al., 1996
51	Canolo Nuovo	38°18'43"N	16°09'56"E	660 m asl	Calabria				Holocene	Gruger, 1977; Schneider, 1985
52	Le Castella	38°14'47"N	16°04'11"E	231 m asl	Calabria				Pleistocene	Bertoldi, 1977; Bertoldi et al., 1989; Raffi and Rio, 1980; Rio, 1982
53	Lago di Preola	37°38'19"N	12°37'08"E	20 m asl	Sicily				Holocene	Sadori et al., 2011
54	Lago di Pergusa	37°31'13"N	14°17'56"E	570 m asl	Sicily				Holocene	Sadori et al., 2013b
55	Punta Piccola	37°16'47"N	13°38'24"E	9 m asl	Sicily				Zanclean to Piacenzian	Combourieu-Nebout et al., 2004; Brolsma, 1978; Hilgen, 1987; Castradori et al., 1998
55	Capo Rossello composite section	37°17'47"N	13°29'24"E	77 m asl	Sicily				Pliocene to Early Pleistocene	Bertoldi, 1985a; Guerrero et al., 1984; Bertoldi et al., 1989; Cita and Gartner, 1973; Hilgen and Langereis, 1988; Caruso, 2004; Cita et al., 2008
56	Monte San Giorgio	37°14'55"N	14°30'34"E	496 m	Sicily				1.23 to 1.095 Ma	Dubois, 2001
57	Monte San Nicola (Gela)	37°15'34.5"N	14°12'48.2" E	394 m asl	Sicily				Early Pliocene	Bertoldi, 1985a; Bertoldi et al., 1989
58	Marine core MD 01-2797	36°57'N	11°40'E	771 m wd	Siculo-tunisian strait				Tarantian-Holocene	Desprat et al., 2013

in red, pollen data included in this paper

wd: water depth N/A not found
asl: above sea level* References including palynology are in bold;
other references in italic




Fig. 3. a: Dominant vegetation during warm (interglacial, squares) and cold (glacial, stars) stages in Italy for the three main sub-series from Pliocene to Early Pleistocene. Orange line corresponds to the latitudinal limit of 42.5°N.

Glacial/Interglacial (G/I) cycles, beginning in the Pleistocene, contributed to the individualization of the Mediterranean climate conditions during the mesic interglacials and dry glacials (Pons et al., 1995).

Modern Mediterranean taxa were present, but only sporadically, during the Paleogene (Fig. 5). Mediterranean taxa have been present in the western Mediterranean since the Paleocene, although diversification of the Mediterranean flora followed the end of the Oligocene (Quézel and Médail, 2003 and references therein). Oligocene fossils of

Oleaceae (pollen and leaves) have been reported from Northern Italy (Sachse, 2001). However, development of truly Mediterranean vegetation occurs only later, during the Miocene, with the weak onset of summer aridity favouring establishment of such vegetation in Italy and throughout the Mediterranean basin (Pons et al., 1995; Quézel and Médail, 2003 and references therein).

Although xerophytic taxa have been reported from Miocene deposits in the northern Mediterranean area (e.g. de Saporta, 1889;




Fig. 3 b: Dominant vegetation during warm (squares) and cold (stars) stages in Italy for the three main sub-series from the middle Pleistocene to modern. Orange line corresponds to the latitudinal limite of 42.5°N.

Bessedik, 1985), semi-arid associations were a minor component in the rich tropical vegetation that occupied the Mediterranean region at that time. Arid or semi-arid associations are not a major feature during the MSC (e.g. Bertini, 2006; Fauquette et al., 2006, 2007; Bertini and Martinetto, 2008, 2011) either, although in some intervals (e.g. close to 5.5 Ma) aridity appears to have promoted the expansion of open vegetation including steppe taxa such as *Lygeum* (Bertini, 2006). The expansion of semi-arid associations across the Mediterranean region is likely related to: (1) the development of a Mediterranean climate during the Pliocene; and (2) the periodic occurrence of aridity since the onset of the Pleistocene (Pons et al., 1995). Semi-arid plant communities developed during the Pliocene and expanded at low to middle altitudes during the middle Pleistocene.

4.2. The Pliocene: setting the stage

Although a diverse Pliocene flora is found in Italian sites after the MSC, while pollen data are available from several sites in Northern Italy they are scarce in Southern Italy (Fig. 3a and b; Table 1) rendering difficult any vegetation synthesis across the entire peninsula (e.g. Bertini, 2010; Bertini et al., 2010 and reference therein).

Pliocene forests in the north were composed of rare tropical to common subtropical taxa, such as *Taxodium*-type, mixed with temperate trees (Zheng and Cravatte, 1986; Zheng, 1990; Bertini, 2001; Fauquette and Bertini, 2003) (Figs. 3a and 4a). Swamp environments were widespread and herbs were a minor component of the vegetation (Fig. 6a and b). After 3 Ma, following marine evidence of cooling, forest of a montane character developed, with major increases in *Picea*




Fig. 4. a: Vegetation changes in Northern and Southern Italy using representative pollen diagrams from 5 Ma to 0.9 Ma. A, decrease in *Taxodium*-type and increase in montane trees; B, onset of decrease in “*Taxodiaceae*” (*Sequoia*-type) and increase in steppic vegetation; B', extinction of “*Taxodiaceae*” and development of *Cathaya*; C, extinction of tropical forest and *Cathaya*, increases of *Tsuga* and *Quercus*; D, increase in *Quercus* forest and increased representation of *Ericaceae*; E, increase in herbs.




Fig. 4 b: Vegetation changes in Northern and Southern Italy using representative pollen diagrams from 1.2 Ma to 0 Ma. E, increase in herbs; F, increase in *Quercus* and extinction of *Tsuga*; G, increase in *Abies* and *Picea*; H, increase in *Fagus*, development of Mediterranean forest, expansion of open vegetation and steppic vegetation.




Fig. 5. Development of the Mediterranean flora and climate in the Mediterranean basin (modified from Quézel and Médail, 2003; Sadori et al., 2013a,b).

followed by *Cedrus* and *Tsuga*, while *Taxodium*-type forest declined (Bertini, 2001, 2010).

There are few Pliocene vegetation records from Southern Italy, mostly from parts of the far south. Thus, on the island of Sicily (the southernmost region of Italy) at Punta Piccola (Combourieu-Nebout et al., 2004) and Capo Rossello (Guerrera et al., 1984; Bertoldi, 1985a; Bertoldi et al., 1989; Suc et al., 1995) open herbaceous vegetation already had expanded during the Pliocene, although steppic taxa remained sporadic. *Quercus* forest was here restricted to mountains, and contained relict subtropical taxa. Further information is needed to improve our understanding of change in Southern Italy during this interval, in particular to reveal the extent of open vegetation at this time. The contrast between northern and far southern records supports the existence of a north–south climate gradient in Italy during the Pliocene, similar to the broader Mediterranean climate pattern at this time (Fauquette et al., 2007). These records also support the existence of an east–west climate gradient in the Mediterranean basin suggested by other Neogene palynological records (Suc et al., 1995; Bertini, 2006; Fauquette et al., 2006, 2007; Bertini, 2010). Climatic conditions during the Early Pliocene were predominantly subtropical, with year-round moisture and warm temperatures (e.g. Fauquette and Bertini, 2003). Mean annual temperatures were between 12 and 20 °C in Northern Italy and exceeded 22 °C in Sicily (Fauquette et al., 1999, 2007). Annual precipitation ranged from 1100 to 1400 mm in the north to ~600 mm in the south (Fauquette et al., 1999, 2007). Thus while the extent of seasonality is unknown, mean annual climate values were similar to modern values.

4.3. The Pleistocene: the onset of recurrent drought and its influence on Mediterranean ecosystems

4.3.1. The Early Pleistocene (EP, 2.588–0.781 Ma, Gelasian and Calabrian) and the regression of subtropical trees

The development of the Arctic ice cap at the beginning of Pleistocene had significant impacts on global climate. The EP corresponds to the initiation of the G/I cycle that has largely driven climate variability on multi-millennial time-scales and that is clearly represented in $\delta^{18}\text{O}$ records from marine sediment cores (for the Mediterranean Sea, see Lourens et al., 1996, 2004) (Fig. 4a). In the Mediterranean, especially in Italy, geological processes, such as Apennine uplift and sea level change, further modified these cyclic processes, resulting in further changes in vegetation composition and structure. Several records have illustrated the occurrence and dynamics of climate cycles during this interval (Combourieu-Nebout, 1993, 1995; Fusco, 1996; Combourieu-Nebout et al., 2000; Bertini, 2001, 2003; Capraro et al., 2005; Fusco, 2007; Joannin et al., 2007; Bertini, 2010, 2013; Bellucci et al., 2014). The start of G/I cycles, and especially the occurrence of cold glacial stages, favoured an increase in steppic taxa that has continued throughout the Pleistocene and up to the present. Over the same interval, forest diversity declined as a result of a progressive decline in, and loss of, subtropical taxa during the Early and Middle Pleistocene (Fig. 3a). As noted above, the north–south climate gradient, marked by increasing aridity towards the south, was already well established by this time (Figs. 3a and 4a) (Fusco, 2007).

During the EP, Mediterranean taxa (mainly *Quercus ilex* accompanied by *Olea*, *Pistacia* and *Cistus*) were present although not abundant in fossil pollen assemblages, (e.g. Combourieu-Nebout, 1995; Magri et al., 2010; Corrado and Magri, 2011). These taxa were not a major component of the vegetation during either interglacial or glacial stages of the EP and probably occurred only at low altitude and/or near the coast. They may, however, have also occurred scattered through the warm-temperate forest and have persisted there during glacial stages.

In the north, moist conditions along the Po valley enabled persistence of swamp environments within the Po valley during interglacial, supporting *Taxodium*-type forests. These swamps were also occasionally present during glacial of the EP (Fusco, 1996, 2007; Fig. 3a, see event A in Fig. 4a; Fig. 6a and b, Table 2). Conifer forests with *Picea* and *Tsuga* extended from higher towards lower altitudes (Fig. 6a; e.g. Fusco, 2010 and references therein). Declines in subtropical swamp forest began around 2.8 Ma, at the time of the first expansion of high altitude conifer forest (Fig. 4a see event A, Table 2). This expansion was marked especially by increased *Picea* observed at sites such as Stirone (Bertini,

2001), and, in central Italy, at sites in the Upper Valdarno (Bertini, 2010, 2013). The expansion of conifers in the north reflects cooling, but the sparse occurrence of open vegetation even during peak glacial stages indicates that there was no marked increase in aridity there. According to Fusco (2010), expansions and contractions of the conifer forests mimic marine $\delta^{18}\text{O}$ variations which are mainly controlled by worldwide temperature changes. In Northern Italy, however, glacial stages saw significant expansions of steppic taxa, especially *Artemisia* (e.g. Bertini, 2010, 2013), indicating relatively arid conditions at those times. Deciduous trees and conifers dominated forests in the north at 2 Ma, marking a second step in vegetation change (e.g. Fusco, 2007). After around 1.4 Ma, interglacial in the Alps were marked by the presence of Juglandaceae (mainly *Carya*), reflecting increased humidity during these stages after that time (e.g. Ravazzi and Rossignol-Strick, 1995; Fusco, 2007).

Subtropical forests associated with elements of the deciduous forests (especially *Quercus*), in the south expanded at low to middle altitudes during interglacial. Conifer forests continued to develop at high




Fig. 6. a: Altitudinal vegetation profiles from the Pliocene to the Holocene at latitudes above 42.5°N.




Fig. 6 b: Dominant vegetation during warm (squares) and cold (stars) stages in Italy for the three main sub-series from the middle Pleistocene to modern. Orange line corresponds to the latitudinal limite of 42.5°N.

altitudes, while herbaceous taxa were limited to coastal fringes (Fig. 6b; Combourieu-Nebout et al., 2000). During glacials, steppic taxa colonised low altitudes, subtropical and deciduous forests were patchy at middle altitudes, and conifer forests dominated at high altitudes, expanding from higher mountain sites occupied during interglacial stages (Fig. 6b). Mountain elevations were still too low to permit the development of alpine tundra (Fauquette and Combourieu-Nebout, 2013). Climate oscillations were the principal (but not exclusive) driver of vegetation change (e.g. Bertini, 2003; Capraro et al., 2005; Bertini, 2010). Shifts between forest and open vegetation clearly following the G/I cycles driven, during the EP, by obliquity (Fig. 4a; Fig. 6a and b; Combourieu-Nebout et al., 1990; Combourieu-Nebout and Vergnaud-Grazzini, 1991; Combourieu-Nebout, 1993, 1995; Fusco, 2007; Joannin et al., 2007; Leroy, 2007; Tzedakis, 2007; Joannin et al., 2008).


Subtropical trees still represented the principal forest component at the onset of the EP. Thereafter “Taxodiaceae” progressively declined, with *Taxodium*-type decreasing markedly at the Pliocene/Pleistocene boundary followed by *Sequoia*-type at the transition to the middle

Calabrian (Fig. 3a, see events A and B in Fig. 4a; Fig. 6a and Table 2). The onset of the decline in *Sequoia*-type in southern Italy at around 2.45 Ma coincides with an intensification of sea surface cooling in the Mediterranean, marked by recurrent increases in $\delta^{18}\text{O}$ values (see B event in Fig. 4a; Lourens et al., 1996). Successive cold intervals at the beginning of the Pleistocene likely stressed subtropical trees, resulting in their progressive decline, although they persisted in some localities until at least 1.66 Ma (e.g. *Cathaya*; Combourieu-Nebout et al., 1990; Combourieu-Nebout and Vergnaud-Grazzini, 1991; Bellucci et al., 2014), and possibly even later (Capraro et al., 2005; Corrado and Magri, 2011) (Fig. 4a see changes from events B to B’). In China today, where *Cathaya* and “Taxodiaceae”, including *Sequoia*-type (e.g. *Metasequoia*), occur in the same areas, they are found in distinct altitudinal belts, with *Cathaya* in a higher altitude belt than that occupied by “Taxodiaceae” (Wang, 1961, 1986). Thus, *Cathaya* development at the expense of “Taxodiaceae” in Italy during the EP probably reflects a progressive cooling of interglacial optima (Combourieu-Nebout and Vergnaud-Grazzini, 1991). This inference corresponds to increased

Table 2

Principal vegetation changes in Italy from early Pleistocene to Holocene, along with the inferred climate.

	Event	Age	Vegetation of North Italy	Vegetation of South Italy	Climate
	–	Holocene	Mixed temperate forest	Mediterranean forest	Temperate to Mediterranean
	H	~0.2 Ma	↑ <i>Abies</i> and <i>Picea</i> in Alps ↑ herbs and steppic taxa during G	↑ <i>Fagus</i> and ↑ Mediterranean taxa during IG, ↑ steppe and open xeric vegetation during G	IG, temperate to Mediterranean G, cold and dry
	G	~0.4–0.5 Ma	–	↑ <i>Abies</i> and <i>Picea</i>	IG, temperate
	F	~0.7 Ma	Extinction of the last exotic subtropical taxa and deciduous forest domination during IG ↑ Conifers (<i>Abies</i> and <i>Picea</i>) in the Alps during G	↑ <i>Quercus</i> forest taxa during IG Extinction <i>Tsuga</i> ↑ herbs during G	G, cool and dry
	E	~1.2 Ma	–	↑ Herbs	IG, temperate
	D	~1.3–1.4 Ma	exotic subtropical taxa still present (<i>Carya</i>) during IG	↑ Ericaceae ↑ montane taxa <i>Tsuga</i>	G, cool–temperate and/or dry
	C	~1.6 Ma	–	Extinction <i>Cathaya</i> and slight ↑ <i>Quercus</i> during IG	IG, temperate
	B'	~2 Ma	↑ <i>Quercus</i> forest taxa, persistence of <i>Taxodium</i> -type in the Po valley	Extinction "Taxodiaceae" (<i>Sequoia</i> -type) and ↑ <i>Cathaya</i> during IG Steppic taxa during G	IG, temperate to subtropical G, cool–temperate and/or dry
	B	~2.4 Ma	↓ <i>Sequoia</i> -type during IG, Onset ↑ Steppic taxa during G ↑ <i>Picea</i> and <i>Tsuga</i>	Onset ↓ <i>Sequoia</i> -type during IG, Onset ↑ Steppic taxa during G	IG, subtropical G, cool–temperate and/or dry
	A	~2.8 Ma	↑ montane trees (<i>Abies</i> , <i>Picea</i> , <i>Tsuga</i>), ↓ "Taxodiaceae" (<i>Taxodium</i> -type and <i>Sequoia</i> -type) Humid subtropical forest, swamps with <i>Taxodium</i> -type	↓ <i>Taxodium</i> -type and ↑ <i>Sequoia</i> -type Open vegetation (Sicily) and <i>Quercus</i> forest with subtropical taxa on the mountains	IG, subtropical G, cool–temperate and/or dry tropical to subtropical
		Before 3 Ma			



G, Glacial
IG, interglacial


interglacial $\delta^{18}\text{O}$ values seen in marine records indicating cooler sea surface temperatures during interglacial optima (see the Oxygen isotope record in Fig. 3a). At the beginning of the Pleistocene, conifers were probably confined to the highest altitude sites in the mountains of Southern Italy, with *Abies*, *Picea*, *Cedrus* and *Tsuga* increasing during the Calabrian, and *Cathaya* declining around 1.6 Ma (Comboureu-Nebout et al., 1990; Comboureu-Nebout and Vergnaud-Grazzini, 1991). Today, when both are found in the same region, *Tsuga* is found at higher elevations than *Cathaya* (Wang, 1961). Thus, as with Taxodiaceae and *Cathaya*, the changing vegetation composition indicates a cooling of interglacial optima that again coincided with increases in interglacial $\delta^{18}\text{O}$ values. Vegetation was again re-organized during the middle Calabrian, around 1.3–1.4 Ma, with the expansion of *Quercus* mixed forest (see events C and D in Fig. 4a; Fig. 4b and Table 2). Higher altitude forests with *Tsuga* persisted and Ericaceae increased in parallel with herbs, while *Carya* declined rapidly after 1.3 Ma (see event E in Fig. 4b; e.g. Dubois, 2001; Joannin et al., 2007, 2008; Corrado and Magri, 2011).

EP climate reconstructions from pollen indicate a subtropical climate sites in Southern Italy. Winters were mild during both glacial and interglacial stages, with mean temperatures above 5 °C (Klotz et al., 2006 and

this paper), although glacials were slightly cooler and drier than interglacials (Fig. 7, box plots 52–76 and 81–100). Temperatures declined around 2 Ma (Fig. 7), with a slight cooling during interglacial winters and sharp declines in precipitation during both glacial (between box plots 52–78 and 80–100) and interglacial stages (between box plots 43–79 and 81–101). Climate reconstructions indicate another cooling, between 1.4 and 1.3 Ma, with winter temperatures decreasing at both interglacial maxima (Fig. 7, see difference between box plots 41–43 and 45–79) and glacial minima (Fig. 7, see difference between box plots 42–46 and 52–78). During the same interval, annual precipitation during both interglacial and glacial stages decreased (Fig. 7).

4.3.2. The middle Pleistocene (MP – 0.781–0.126 Ma, Ionian) and the development of lowland deciduous and montane forests

The 41 kyr G/IG cycles of the EP were replaced by 100 kyr cycles during the MP, with the length of glacial stages increased (Tzedakis, 2005, 2007; Leroy, 2007; Tzedakis et al., 2012). This change is evident in several Italian records (e.g. Follieri et al., 1988, 1989; Russo Ermolli et al., 1995; Russo Ermolli and Cheddadi, 1997; Magri, 1999; Magri and Sadori, 1999; Muttoni et al., 2007; Ravazzi et al., 2009; Fusco, 2010; Magri, 2010; Russo Ermolli et al., 2010a; Magri and Palombo, 2013;



L: Late M: Middle E: Early P: Pleistocene Hol: Holocene

Tar: Tarantian Ion: Ionian Cal: Calabrian Gel: Gelasian

★ present-day values

Valle di Castiglione, Boiano, Vallo di Diano, Montalbano, Santa Lucia, Crotone

Fig. 7. Climate changes in Southern Italy from Early Pleistocene to present day. Inferred values are presented as box plots summarising interglacials: Holocene (Hol); sub-stage 5e (0.123–0.130 Ma); stages 7–9 (0.191–0.337 Ma); stage 11 (0.374–0.424 Ma); stages 13–15 (0.478–0.563 Ma); stages 23–27 (0.900–0.970 Ma); stages 41–43 (1.320–1.362 Ma); stages 45–79 (1.405–2.103 Ma); and stages 81–101 (2.146–2.554 Ma); and for glacials: stages 2–4 (0.014–0.071 Ma); stages 6–8 (0.130–0.300 Ma); stage 12 (0.424–0.478 Ma); stages 14–16 (0.533–0.676 Ma); stages 22–28 (0.866–1.014 Ma); stages 40–46 (1.286–1.405 Ma); stages 52–78 (1.530–2.043 Ma); and stages 80–100 (2.125–2.540 Ma). Ages of the boxplot-intervals are from Lisiecki and Raymo (2005). Interglacials are plotted in red and glacials in blue in two separate diagrams. Interglacials and glacials are shown for the whole time series in the central and righthand columns respectively; the lefthand column shows the last G/IG cycle at Monticchio and the Last deglaciation and Holocene for core MD 91–917. Bold lines represent the median, fine lines connect the means. The dotted line marks the extreme value interval (interquartile range no more than 1.5) and outliers are indicated by small empty circles.

Orain et al., 2013). Plant communities during the MP were very different from those of the late Calabrian, with deciduous *Quercus* forests extending across the peninsula during interglacial stages and increased herbaceous cover during glacial stages. Mediterranean taxa were present, with *Quercus ilex* as the principal taxon, and they increased in representation during interglacial stages.

Deciduous forests dominated in Northern Italy during the MP. The increased length and severity of glacial stages effectively extirpated subtropical taxa from the region and supported the expansion of conifer forests in the Alps (e.g. Muttoni et al., 2007; Ravazzi et al., 2009) (Fig. 4b; Fig. 3a and b). Conifers expanded downslope during cold intervals while at lower elevations there was an open

herbaceous vegetation mixed with steppic elements (Fig. 4b see event F, Table 2). Ericaceae became now a significant component of the open vegetation (Fig. 6a).

Deciduous forest dominated in the South during MP interglacials and *Fagus* began to increase in relative abundance. Subtropical trees were absent. *Tsuga* was present sporadically as a relic of the older subtropical humid vegetation (Fig. 4b see event F, Fig. 3a and b; Fig. 6b and Table 2). *Carya* and *Pterocarya* were still found, although rarely, possibly in refuge areas (e.g. Orain et al., 2013). Conifers, including *Abies*, became established at higher altitudes and expanded at middle altitudes during glacial stages (Fig. 4 see event G, Fig. 6b) (Orain et al., 2013). During the longer, colder and drier glacial stages herbs colonised lower elevations and land that was exposed by falling sea levels. Steppic vegetation proportions increased during the glacial stage after 0.3–0.2 Ma, a signal of increasing drought intensity (Fig. 4b see after event H).

Pollen-inferred climate indicates low temperatures in both glacial and interglacial stages. Maxima for MP interglacial stages are near the lowest values observed during the LP glacials. MP glacial stages experienced much lower temperatures (Fig. 7). Cool interglacials that were longer than previous interglacials (Tzedakis, 2007; Tzedakis et al., 2012) may explain the increase in conifers, the expansion of *Quercus* forest at mid-altitude and the increase in *Fagus* (e.g. Russo Ermolli et al., 1995; Russo Ermolli and Cheddadi, 1997; Magri, 1999; Magri and Sadori, 1999; Russo Ermolli et al., 2010a). The increase in Ericaceae and herbs in Southern Italy may also be related to the longer glacials (Fig. 6a and b). Pollen inferred climate reconstructions show near-modern annual precipitation values during interglacials, whereas glacials were dry. Precipitation seasonality is inferred for the interglacials (Fig. 7).

Although pollen based reconstructions exhibit climate oscillations, with warm/humid interglacials and cold/dry glacials during the MP, some interglacials appear to have experienced cooler winters than the glacials, especially marine isotope stage (MIS) 11 (Fig. 7). Precipitation during MIS 11 appears to have been slightly lower during winter and higher in summer comparing to other interglacials from the same period. Reconstructed MTCO values for MIS 11 are the lowest of the interglacial box plot series, whereas reconstructed precipitation is

greater than for preceding stages. The MIS 11 reconstructions come from pollen assemblages in the Boiano section and need to be confirmed by more analyses of other time-series since this is not a common feature in G/I alternation. The Boiano basin may have been a refuge for vegetation during MIS 11, potentially biasing estimates because of the presence of taxa such as *Carya* that persisted at this site characterised by its topographic situation, whereas regional climate was less suited to their presence (Orain et al., 2013). More recent G/I cycles show the expected patterns of opposition between interglacial and glacial climatic conditions, although the contrast in reconstructed climate between glacial and interglacial stages is less than expected. The lowest reconstructed glacial MTCO values fall during MIS 6–8 (Fig. 7).

4.3.3. The Late Pleistocene (LP – 0.125–0.01 Ma, Tarantian) and the persistence of drought

Several pollen records capture the LP in Italy (e.g. Mullenders et al., 1996; Follieri et al., 1998; Allen et al., 1999; Magri, 1999; Magri and Sadori, 1999; Allen and Huntley, 2000; Kent et al., 2002; Ravazzi, 2002; Brauer et al., 2007b; Allen and Huntley, 2009; Pini et al., 2009a, b) and demonstrate the increasing extent, duration and recurrence of drought through the regular expansion of steppe/semi-desert over large areas in Italy since MIS 11. The LP interglacial/glacial cycle was expressed as an alternation between deciduous forest and steppe both in Northern and Southern Italy (Fig. 4b). Mediterranean taxa were well represented during the warm interglacials but restricted during the last glacial.

In Northern Italy the proportion of conifers increased from the Po valley towards the Alps (Fig. 3a and b; e.g., Mullenders et al., 1996; Pini et al., 2009a,b). *Picea* and *Abies* occupied upper elevations and were mixed with deciduous *Quercus* at middle to lower altitudes during the last interglacial (Ravazzi, 2002). Herbaceous and steppic vegetation occupied northern valleys during glacials. Mediterranean taxa were rarely present in Northern Italy, even though they may be considered to be part of the regional vegetation.

In Southern Italy the last interglacial was marked by the development of deciduous *Quercus* forest at middle altitudes, with a strong increase in *Fagus* (Fig. 3b see after event H, Figs. 6b and 8; e.g. Watts et al., 1996; Follieri et al., 1998; Magri and Sadori, 1999; Watts et al.,




Fig. 8. Representative vegetation changes during the last climate cycle in Northern and Southern Italy.

2000; Allen and Huntley, 2000; Allen et al., 2002; Brauer et al., 2007a,b). *Abies* and *Fagus* both increased at higher altitudes in the Apennines, while at low altitudes Mediterranean communities expanded. Herbs and steppic taxa were probably restricted to the coast. Chenopodiaceae increased in importance within the open vegetation assemblages, especially during glacials, probably expanding in an edaphic fringe near the coast and over the land exposed by sea level decreases (Fig. 4b; e.g. Follieri et al., 1998; Allen et al., 1999; Magri and Sadori, 1999; Allen and Huntley, 2000; Brauer et al., 2007b; Allen and Huntley, 2009). Mediterranean forest was established and remained stable at middle altitude, especially south of 43°N. During MIS 3, peaks in abundance of steppic elements regularly indicated changes in vegetation associated with arid intervals (Allen et al., 1999; Fletcher et al., 2010) recognised from the western Mediterranean and concurrent with North Atlantic Heinrich Events observed in the western Mediterranean (e.g. Combourieu Nebout et al., 2002; Sánchez Góni et al., 2002). This clearly indicates the ability of vegetation in the central Mediterranean to respond quickly to abrupt climate events.

Pollen-based climate reconstructions for Southern Italian sites show that MTCO during marine isotope sub-Stage 5e was nearly as warm as during the EP interglacials (Fig. 7). Nevertheless, annual precipitation remained low compared to the earlier interglacials. During the glacial stage, both temperature and precipitation values were very low, corresponding to the lowest values obtained in the box plot record (Fig. 7). This was probably linked to recurrent Mediterranean cooling, along with increased aridity induced by the global climate effects of Heinrich Event discharges in the North Atlantic (e.g. Combourieu-Nebout et al., 2002; Sánchez Góni et al., 2002).

4.3.4. The Last deglaciation and Holocene: the installation of the Mediterranean climate seasonality and human pressure on Mediterranean environments

The last deglaciation and the Holocene in Italy are well described by pollen records. These records show the step-wise development of deciduous *Quercus* forests in Northern Italy (e.g. Joannin et al., 2013, 2014) and of its partial replacement by Mediterranean mixed forests in Southern Italy (e.g. Grüger, 1975, 1977; Rossignol-Strick and Planchais, 1989; Rossignol-Strick et al., 1992; Zonneveld, 1996; Combourieu-Nebout et al., 1998; Magri and Sadori, 1999; Sadori and Narcisi, 2001; Allen et al., 2002; Oldfield et al., 2003; Drescher-Schneider et al., 2007; Sadori et al., 2011; Di Rita and Magri, 2012; Joannin et al., 2012; Mercuri et al., 2012; Combourieu-Nebout et al., 2013; Di Rita et al., 2013; Mercuri et al., 2013; Sadori et al., 2013b and references therein) (Fig. 3a, b; Figs. 4b and 8). The early Holocene summer insolation maximum was marked by a humid event, expressed by increases in Po discharges into the Adriatic Sea and increases in high elevation forests (e.g. Combourieu-Nebout et al., 1998, 2013). After 4.2 kyr BP, pollen records show increasing dryness, expressed as an expansion of herbs and Mediterranean taxa. We see the onset of present-day precipitation seasonality and increases in human impacts expressed through deforestation and agriculture which can induce a possible bias in the pollen-based reconstructions for this period (e.g. Sadori et al., 2004; Di Rita and Magri, 2009; Sadori et al., 2011, 2013b; Combourieu-Nebout et al., 2013; Mercuri et al., 2013; Joannin et al., 2014). Pollen-based reconstructions show the modern Mediterranean climate regime establishing, with an inversion of winter and summer precipitation trends after 4.2 kyr BP, well illustrated by the regional record from marine core MD 90-917 (Fig. 7; Combourieu-Nebout et al., 2013). Italian precipitation regime changes and aridification fit the scenario of Mediterranean Holocene climatic changes outlined in Pons and Quézel (1985); Jalut et al. (2000, 2009). The combination of aridification and increasing seasonality have played a major role in driving major and all too recent vegetation changes in Italy and, along with human impacts, will influence Mediterranean ecosystems in the future.

5. Conclusion

Pollen records are used to show the step-wise changes in vegetation patterns on the Italian peninsula over the past 5 million years. These pollen records show the relationships between successive vegetation changes and climate variations (temperature and precipitation) in the Mediterranean region.

Based on vegetation composition, a north–south climate gradient has existed on the Italian peninsula since at least the Pliocene. After a warm and humid Pliocene, the Early Pleistocene, characterised by the beginning of G/I cycles, experienced a progressive decline in subtropical taxa in the sequence: first *Taxodium*-type (~3–2.8 Ma); *Sequoia*-type (~2 Ma); and finally *Cathaya* (after 1.6 Ma). Steppic associations occurred cyclically, expanding during glacial stages. The first step-wise decreases in humidity and winter temperature occurred at around 2 Ma and 1.4–1.3 Ma.

During the Middle and Late Pleistocene, new vegetation communities assembled, marked by conifer forest expansion in the north and the expansion of deciduous *Quercus* forest, with *Fagus* and *Betula*, in the south. Herbaceous and steppic taxa also expanded over a large area, to a more pronounced extent during glacial stages. Further cooling occurred at 0.4–0.5 Ma, with decreasing precipitation and winter temperatures during glacials. Interglacials remained relatively humid.

Modern Mediterranean summer drought was established during the Holocene after 4.2 kyr BP, following humid early- to mid-Holocene climates, the humid character of which was more pronounced in summer.

Acknowledgements

Authors thank the CNRS for financial support. This work was partly supported through CNRS–INSU–Lefe program (INTERMED project), CNRS–MISTRALS program (TerMex part – CYCLAMEN project) and by EU “Past for Future” FP7 project.

This is LSCE contribution N° 4518 and ISEM publication n°2014-180”.

References

- Albianelli, A., Bertini, A., Magi, M., Napoleone, G., Sagri, M., 1995. Il bacino Plio-Pleistocenico del Valdarno Superiore: eventi deposizionali, paleomagnetici e paleoclimatici. *Il Quaternario (Ital. J. Quat. Sci.)* 8 (1), 11–18.
- Allason, B., Carraro, F., Ghibaud, G., Paganelli, A., Ricci, B., 1981. Prove palinologiche dell'età pleistocenica inferiore di depositi “villafranchiani” in Piemonte. *Geogr. Fis. Din. Quat.* 4, 39–47.
- Allen, J.R.M., Huntley, B., 2000. Weichselian palynological records from southern Europe: correlation and chronology. *Quat. Int.* 73 (74), 111–125.
- Allen, J.R.M., Huntley, B., 2009. Last interglacial palaeovegetation, palaeoenvironments and chronology: a new record from Lago Grande di Monticchio, southern Italy. *Quat. Sci. Rev.* 28, 1521–1538.
- Allen, J.R.M., Brandt, U., Brauer, A., Hubberten, H.-W., Huntley, B., Keller, J., Kraml, M., Mackensen, A., Mingram, J., Negendank, J.F.W., Nowaczyk, N.R., Oberhänsli, H., Watts, W.A., Wulf, S., Zolitschka, B., 1999. Rapid environmental changes in southern Europe during the last glacial period. *Nature* 400, 740–743.
- Allen, J.R.M., Watts, W.A., McGee, E., Huntley, B., 2002. Holocene environmental variability – the record from Lago Grande di Monticchio, Italy. *Quat. Int.* 88, 69–80.
- Amato, V., Aucelli, P.P.C., Cesarano, M., Pappone, G., Rosskopf, C.M., Russo Ermolli, E., 2011. The Sessano intra-montane basin: new multi-proxy data for the Quaternary evolution of the Molise sector of the Central–Southern Apennines (Italy). *Geomorphology* 128, 15–31.
- Amorosi, A., Antoniolli, F., Bertini, A., Marabini, S., Mastronuzzi, G., Montagna, P., Negri, A., Rossi, V., Scarponi, D., Taviani, M., Angeletti, L., Piva, A., Vai, G.B., 2014. The Middle–Upper Pleistocene Fronte Section (Taranto, Italy): an exceptionally preserved marine record of the last interglacial. *Glob. Planet. Chang.* 119, 23–38.
- Arias, C., Bigazzi, G., Bonadonna, F.P., Iaccarino, S., Urban, B., Dal Molin, M., Dal Monte, L., Martolini, M., 1990. Valle Ricca Late Neogene stratigraphy (Lazio region, Central Italy). *Paléobiol. Cont.* 17, 61–68.
- Aucelli, P., Amato, V., Cesarano, M., Pappone, G., Rosskopf, C.M., Russo Ermolli, E., Scarciglia, F., 2011. New morphostratigraphic and chronological constraints for the Quaternary palaeosurfaces of the Molise Apennines (southern Italy). *Geol. Carpath.* 62, 17–26.
- Baggioni, M., Suc, J.-S., Vernet, J.L., 1981. Le Plio–Pléistocène de Camerota (Italie méridionale): géomorphologie et paléoflores. *Geobios* 14, 229–237.

- Basilici, G., 1997. Sedimentary facies in an extensional and deep lacustrine depositional system: the Pliocene Tiberino Basin, Central Italy. *Sedimentology* 109, 73–94.
- Becker-Platen, J.D., Benda, L., Cepek, P., Daniels, C.H.V., Mengeling, H., Meyer, K.J., Steffens, P., Streif, H., Vinken, R., 1977. Beiträge zur Plio-Pleistozän-Grenzziehung in Mittelitalien. *Giorn. Geol.* 41, 107–114.
- Bellucci, L., Bona, F., Corrado, P., Magri, D., Mazzini, I., Parenti, F., Scardia, G., Sardella, R., 2014. Evidence of late Gelasian dispersal of African fauna at Coste San Giacomo (Anagni Basin, central Italy): Early Pleistocene environments and the background of early human occupation in Europe. *Quat. Sci. Rev.* 96, 72–85.
- Belluomini, G., Manfra, L., Palombo, M.R., 1997. A recent aminochronology of Pleistocene Mammals from Rome area and Isernia-La Pineta deposits (Italy). *Geol. Romana* 33, 73–79.
- Bennett, K., 2008. Pspimpoll and pscomb. Available for download at: <http://www.chrono.qub.ac.uk/psimpoll/psimpoll.html>.
- Benvenuti, M., Degli Innocenti, D., 2001. The Pliocene deposits in the central-eastern Valdelsa Basin (Florence, Italy) revised through facies analysis and unconformity-bounded stratigraphic units. *Riv. Ital. Paleontol. Stratigr.* 107, 265–286.
- Benvenuti, M., Bertini, A., Conti, C., Dominici, S., 2007. Integrated analyses of litho and bio-facies in a Pliocene cyclothemic, alluvial to shallow marine succession (Tuscany, Italy). *Geobios* 40 (2), 143–158.
- Bertini, A., 1994. Messinian–Zanclean vegetation and climate in north-central Italy. *Hist. Biol.* 9, 3–10.
- Bertini, A., 2000. Pollen record from Colle Curti and Cesi: early and middle Pleistocene mammal sites in the Umbro–Marchean Apennine mountains (central Italy). *J. Quat. Sci.* 15, 825–840.
- Bertini, A., 2001. Pliocene climatic cycles and altitudinal forest development from 2.7 Ma in the northern Apennines (Italy): evidences from the pollen record of the Stirone section (~5.1 to ca. 2.2 Ma). *Geobios* 34, 253–265.
- Bertini, A., 2002. Palynological evidence of late Neogene environments in Italy. *Acta Univ. Carol. Geol.* 46, 15–25.
- Bertini, A., 2003. Early to Middle Pleistocene changes of the Italian flora and vegetation in the light of a chronostratigraphic framework. *Il Quaternario* 16, 19–36.
- Bertini, A., 2006. The Northern Apennines palynological record as a contribute for the reconstruction of the Messinian palaeoenvironments. *Sediment. Geol.* 188–189, 235–258.
- Bertini, A., 2010. Pliocene to Pleistocene palynoflora and vegetation in Italy: state of the art. *Quat. Int.* 225, 5–24.
- Bertini, A., 2013. Climate and vegetation in the Upper Valdarno Basin (central Italy) as a response to Northern Hemisphere insolation forcing and regional tectonics in the late Pliocene–early Pleistocene. *Ital. J. Geosci.* 132, 137–148.
- Bertini, A., Martinetto, E., 2008. Messinian to Zanclean vegetation and climate of Northern and Central Italy. *Boll. Soc. Paleontol. Ital.* 47, 105–121.
- Bertini, A., Martinetto, E., 2011. Reconstruction of vegetation transects for the Messinian–Piacenzian of Italy by means of comparative analysis of pollen, leaf and carpological records. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 304, 230–246.
- Bertini, A., Roiron, P., 1997. Evolution de la végétation et du climat pendant le Pliocène moyen en Italie centrale: apport de la palynologie et des macroflore à l'étude du bassin du Valdarno Supérieur (coupe de Santa Barbara). *C. R. Acad. Sci. Paris* 324, 763–771.
- Bertini, A., Ciaranfi, N., Marino, M., Palombo, M.R., 2010. Proposal for Pliocene and Pleistocene land–sea correlation in the Italian area. *Quat. Int.* 219, 95–108.
- Bertolani-Marchetti, D., Accorsi, C.A., Pelosio, G., Raffi, S., 1979. Palynology and stratigraphy of the Plio–Pleistocene sequence of the Stirone River (northern Italy). *Pollen Spores* 21, 149–167.
- Bertoldi, R., 1977. Studio palinologico della serie di Le Castellina (Calabria). *Atti Accad. Naz. Lincei* 62 (4), 535–547.
- Bertoldi, R., 1985a. Palinostatigrafia in sedimenti marini del Pliocene della Sicilia e considerazioni paleoclimatiche. *Atti Accad. Naz. Lincei* 78, 157–164.
- Bertoldi, R., 1985b. Testimonianze palinologiche di età “Villafranchiana” nel deposito fluvio-lacustre di Compiano (Alta Val di Taro). *Acta Natur. Aten. Parm.* 21, 23–30.
- Bertoldi, R., 1988. Una sequenza palinologica di età Rusciniense nei sedimenti lacustri basali del bacino di Aulla-Olivola. *Riv. Ital. Paleontol. Stratigr.* 94, 105–138.
- Bertoldi, R., Castello, F., 1990. Palinoflora di età Villafranchiana inferiore nel deposito continentale di Sesta Godano in Val di Vara (Bacino del F. Magra). *Atti Soc. Tosc. Sci. Nat. Mem.* 97, 31–45.
- Bertoldi, R., Martinetto, E., 1995. Ricerche paleobotaniche (palinologiche e paleocarpologiche) sulla successione “Villafranchiana” del Rio Ca’ Viettone. *Il Quaternario* 8, 403–422.
- Bertoldi, R., Rio, D., Thunell, R., 1989. Pliocene–Pleistocene vegetational and climatic evolution of the south-central Mediterranean. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 72, 263–275.
- Bertoldi, R., Binotti, A., Castello, F., 1994. *Reevesia* and *Itea* in the pollen flora of the Upper Neogene continental deposit at Sarzana (lower Magra valley, Northern Italy). *Rev. Palaeobot. Palynol.* 80, 159–172.
- Bessedik, M., 1985. Reconstitution des environnements miocènes des régions nord-ouest méditerranéennes à partir de la palynologie. (Phd), Univ. Montpellier 2, France (162 pp.).
- Blasi, C., 2010. La vegetazione d'Italia con carta delle Serie di Vegetazione in scala 1: 500 000. Palombi Editore, Rome, Italy, 536 pp.
- Bonin, G., 1981. L'étagement de la végétation dans l'Appennin méridional. *Ecol. Mediterr.* 7, 79–91.
- Borzi, M., Carboni, M.G., Di Bella, L., Florindo, F., Girotti, O., Piccardi, E., Sagnotti, L., 1998. Bio- and magneto-stratigraphy in the Tiber valley revised. *Quat. Int.* 47 (48), 65–72.
- Bossio, A., Costantini, A., Lazzaretto, A., Lotta, D., Mazzanti, R., Mazzei, R., Salvadorini, G., Sandrelli, F., 1993. Rassegna delle conoscenze sulla stratigrafia del Neoaustrotono toscano. *Mem. Soc. Geol. Ital.* 49, 17–98.
- Brauer, A., Mingram, J., Frank, U., Gunter, C., Schettler, G., Wulf, S., Zolitschka, B., Negendank, J.F.W., 2000. Abrupt environmental oscillations during the early Weichselian recorded at Lago Grande di Monticchio, southern Italy. *Quat. Int.* 73 (74), 79–90.
- Brauer, A., Wulf, S., Mangili, C., Moscariello, A., 2007a. Tephrochronological dating of varved interglacial lake deposits from Pianico–Sèllere (Southern Alps, Italy) to around 400 ka. *J. Quat. Sci.* 22, 85–96.
- Brauer, A., Allen, J.R.M., Mingram, J., Dulski, P., Wulf, S., Huntley, B., 2007b. Evidence for last interglacial chronology and environmental change from Southern Europe. *Proc. Natl. Acad. Sci. U. S. A.* 104, 450–455.
- Brauer, A., Mangili, C., Moscariello, A., Witt, A., 2008. Palaeoclimatic implications from micro-facies data of a 5900 varves time series from the Pianico interglacial sediment record, Southern Alps. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 259, 121–135.
- Brenac, P., 1984. Végétation et climat de la Campanie du Sud (Italie) au Pliocène final d'après l'analyse pollinique des dépôts de Camerota. *Ecol. Mediterr.* 10, 207–216.
- Brolsma, M.J., 1978. Quantitative foraminiferal analysis and environmental interpretation of the Pliocene and topmost Miocene on the South coast of Sicily. *Utrecht Micropaleontol. Bull.* 18, 159.
- Brunsfeld, S.J., Soltis, P.E., Soltis, D.E., Gedek, P.A., Quinn, C.J., Streng, D.D., Ranker, T.A., 1994. Phylogenetic relationships among the genera of Taxodiaceae and Cupressaceae: evidence from rbcL sequences. *Syst. Bot.* 19 (2), 253–262.
- Buccheri, G., Capretto, G., Di Donato, V., Esposito, P., Ferruzza, G., Pescatore, T., Russo, E., Molli, E., Senatore, M.R., Sprovieri, M., Bertoldi, M., Carella, D., Madonia, G., 2002. A high resolution record of the last de glaciation in the southern Tyrrhenian Sea: environmental and climatic evolution. *Mar. Geol.* 115, 1–24.
- Canali, G., Capraro, L., Donnici, S., Rizzetto, F., Serandrei-Barbero, R., Tosi, L., 2007. Vegetational and environmental changes in the eastern Venetian coastal plain (Northern Italy) over the past 80,000 years. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 253, 300–316.
- Capraro, L., Asoli, A., Backman, J., Bertoldi, R., Channell, J.E.T., Massari, F., Rio, D., 2005. Climatic patterns revealed by pollen and oxygen isotope records across the Matuyama Brunhes Boundary in the central Mediterranean (southern Italy). In: Head, M.D., Gibbard, P.L. (Eds.), *Early-Middle Pleistocene Transition: the Land–Ocean Evidence*. *Geol. Soc. Lond. Spec. Publ.* 247, 159–182.
- Carloni, G.C., Francavilla, F., Borsetti, A.M., Cati, F., D'Onofrio, S., Mezzetti, R., Savelli, C., 1974. Ricerche stratigrafiche sul limite Miocene–Pliocene nelle Marche centro-meridionali. *Giorn. Geol.* 29 (2), 363–392.
- Caroli, B., Caldera, M., 2007. Vegetation history of Lago Battaglia (Eastern Gargano coast, Italy) during the mid-late Holocene. *Veg. Hist. Archaeobot.* 16, 317–327.
- Carraro, F., Ambrosetti, P., Angela-Franchini, M., Azzaroli, A., Basilici, G., Belluomini, G., Bertoldi, R., Boano, P., Bormioli, D., Campanino, F., Caramiello, R., Cerasoli, M., Ciangherotti, A., Compagnoni, R., Esu, D., Ferrero, E., Ficarelli, G., Forno, M.G., Genovese, G., Giardino, M., Girotti, O., Gliozzi, E., Lanza, R., Mai, D., Manfra, L., Martinetto, E., Masini, F., Moscariello, A., Pavia, G., Perotto, A., Polino, R., Sala, B., Siniscalco, C., Torre, D., Violanti, D., 1996. Revisione del Villafranchiano nell'area tipo di Villafranca d'Asti. *Il Quaternario* 9, 5–120.
- Caruso, A., 2004. Climatic changes during late Pliocene and early Pleistocene at Capo Rossello (Sicily, Italy): response from planktonic foraminifera. In: Coccioni, R., Galeotti, S., Lirer, F. (Eds.), *Proceedings of the First Italian Meeting on Environmental Micropaleontology*. Grzybowski Foundation Special Publication 9, pp. 17–36.
- Castradori, D., Rio, D., Hilgen, F.J., Lourens, L.J., 1998. The global standard stratotype section and point (GSSP) of the Piacenzian Stage (Middle Pliocene). *Episodes* 21, 88–93.
- Chiari, E., Giardini, M., La Posta, E., Papasodaro, F., Sadori, L., 2007. Sedimentology, palynology and new geochronological constraints on Quaternary deposits of the Corvaro intermontane basin (Central Italy). *Rev. Micropaleontol.* 50, 309–314.
- Chiari, E., Giardini, M., Mattei, M., Papasodaro, F., Porreca, M., Sadori, L., 2009. Plio–Quaternary evolution of the high Salto river valley: the Marano de'Marsi unit. *Il Quaternario (Ital. J. Quat. Sci.)* 22 (2), 325–344.
- Christensen, J.H., Hewitson, B., Busuioac, A., Chen, A., Gao, X., Held, I., Jones, R., Kolli, R.K., Kwon, W.-T., Laprise, R., Magaña Rueda, V., Mearns, L., Menéndez, C.G., Räisänen, J., Rinke, A., Sarr, A., Whetton, P., 2007. Regional climate projections. In: Solomon, S., Qin, D., Manning, M., Chen, Z., Marquis, M., Averyt, K.B., Tignor, M., Miller, H.L. (Eds.), *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA.
- Cibin, U., Severi, P., Correggiari, A., Roveri, M., Colalonga, M.L., Fiorini, F., Fusco, F., Pasini, G., 2005. Note Illustrative della Carta Geologica d'Italia alla scala 1:50.000, Foglio 240–241 Forlì-Cervia. Ed. Servizio Geologico, Sismico e dei Suoli Regione Emilia-Romagna, 104 pp.
- Cita, M.B., Gartner, S., 1973. Studi sul Pliocene e sugli strati di passaggio dal Miocene al Pliocene. IV. The stratotype Zanclean. Foraminiferal and nanofossil biostratigraphy. *Riv. Ital. Paleontol. Stratigr.* 79, 503–558.
- Cita, M.B., Capraro, L., Ciaranfi, N., Di Stefano, E., Lirer, F., Maiorano, P., Marino, M., Raffi, I., Rio, D., Sprovieri, R., Stefanelli, S., Vai, G.B., 2008. The Calabrian Stage redefined. *Episodes* 31, 408–419.
- Coltorti, M., Albanelli, A., Bertini, A., Ficarelli, G., Laurenzi, M.A., Napoleone, G., Torre, D., 1998. The Colle Curti Mammal site in the Colfiorito area (Umbria–Marchean Apennine, Italy): geomorphology, stratigraphy, paleomagnetism and palynology. *Quat. Int.* 46 (48), 107–116.

- Comboureu-Nebout, N., Turon, J.L., Zhan, R., Capotondi, L., Londeix, L., Pahnke, K., 2002. Enhanced aridity and atmospheric high-pressure stability over the western Mediterranean during the North Atlantic cold event of the past 50 kyr. *Geology* 30, 863–866.
- Comboureu-Nebout, N., 1993. Vegetation response to upper Pliocene glacial/interglacial cyclicity in the central Mediterranean. *Quat. Res.* 40, 228–236.
- Comboureu-Nebout, N., 1995. Réponse de la végétation de l'Italie méridionale au seuil climatique de la fin du Pliocène d'après l'analyse pollinique haute résolution de la section de Semaforo (2.46 à 2.1 Ma). *C. R. Acad. Sci. Paris* 321, 659–665.
- Comboureu-Nebout, N., Vergnaud-Grazzini, C., 1991. Late Pliocene northern hemisphere glaciations: the continental and marine responses in the central Mediterranean. *Quat. Sci. Rev.* 10, 319–334.
- Comboureu-Nebout, N., Semah, F., Djubiantono, T., 1990. La limite Pliocène/Pléistocène: précisions magnétostratigraphiques par l'étude série de la coupe type de Vrica (Crotone, Italie). *C. R. Acad. Sci.* 311, 851–857.
- Comboureu-Nebout, N., Siani, G., Paterne, M., Turon, J.L., 1998. A high resolution record of the Last Deglaciation in the Central Mediterranean Sea: palaeovegetation and palaeohydrological evolution. *Quat. Sci. Rev.* 17, 3–4.
- Comboureu-Nebout, N., Fauquette, S., Quézel, P., 2000. What was the Late Pliocene Mediterranean climate like: a preliminary quantification from vegetation. *Bull. Soc. Geol. Fr.* 171, 271–277.
- Comboureu-Nebout, N., Turon, J.L., Zhan, R., Capotondi, L., Londeix, L., Pahnke, K., 2002. Enhanced aridity and atmospheric high-pressure stability over the western Mediterranean during the North Atlantic cold event of the past 50 kyr. *Geology* 30, 863–866.
- Comboureu-Nebout, N., Foucault, A., Mélières, F., 2004. Vegetation markers of palaeoclimate cyclical changes in the Pliocene of Punta Piccola (Sicily, Italy). *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 214 (1–2), 55–66.
- Comboureu-Nebout, N., Peyron, O., Bout-Roumazielle, V., Goring, S., Dormoy, I., Joannin, S., Sadori, L., Siani, G., Magny, M., 2013. Holocene vegetation and climate changes in central Mediterranean inferred from a high-resolution marine pollen record (Adriatic Sea). *Clim. Past* 9, 2023–2042.
- Corrado, P., Magri, D., 2011. A late Early Pleistocene pollen record from Fontana Ranuccio (central Italy). *J. Quat. Sci.* 26, 335–344.
- Cremaschi, M., 1983. La serie pleistocenica di Isernia la Pineta (Molise) e la posizione stratigrafica dei suoli d'abitato paleolitici in essa inclusi. In: Peretto, C., Terzani, C., Cremaschi, M. (Eds.), *Isernia la Pineta, un accampamento più antico di 700 000 anni*. Calderini, Bologna, pp. 49–62.
- Cremaschi, M., Peretto, C., 1988. Les sols d'habitat du site paléo-lithique d'Isernia la Pineta (Molise, Italie centrale). *l'Anthropologie* 92, 1017–1040.
- Cremaschi, M., Ravazzi, C., 1995. Nuovi dati stratigrafici e geocronologici sul Bacino di Lefte (Prealpi Lombarde, Bergamo). *Il Quaternario* 167–182.
- Daget, P., 1977. Le bioclimat méditerranéen: caractères généraux, modes de caractérisation. *Vegetatio* 34 (1), 1–30.
- de Beaulieu, J.L., Andrieu-Ponel, V., Cheddadi, R., Guiter, F., Ravazzi, C., Reille, M., Rossi, S., 2006. Apport des longues séquences lacustres à la connaissance des variations des climats et des paysages pléistocènes. *C. R. Palevol* 5, 65–72.
- de Saporta, G., 1889. Dernières adjonctions à la flore fossile d'Aix-en-Provence, 2, Masson eds, Paris, 192 pp.
- Delitala, M.C., Fornaseri, M., Nicoletti, M., 1983. Datazioni argon — potassio sulla serie pleistocenica di Isernia la Pineta. In: Peretto, C., Terzani, C., Cremaschi, M. (Eds.), *Isernia la Pineta, un accampamento più antico di 700 000 anni*. Calderini, Bologna, pp. 65–66.
- Desprat, S., Comboureu-Nebout, N., Essallami, L., Sicre, M.A., Dormoy, I., Peyron, O., Siani, G., Bout-Roumazielle, V., Turon, J.L., 2013. Deglacial and Holocene vegetation and climatic changes at the southernmost tip of the Central Mediterranean from a direct land-sea correlation. *Clim. Past* 9, 767–787.
- Di Bella, L., Carbonia, M.G., Bergamin, L., Iamund, F., 2005. The Early Pleistocene in Latium (Central Italy): palaeoecology from benthic foraminiferal record. *Quat. Int.* 131, 23–34.
- Di Donato, V., Esposito, P., Russo-Ermolli, E., Scarano, A., Cheddadi, R., 2008. Coupled atmospheric and marine palaeoclimatic reconstruction for the last 35 ka in the Sele Plain—Gulf of Salerno area (southern Italy). *Quat. Int.* 190, 146–157.
- Di Rita, F., Magri, D., 2009. Holocene drought, deforestation, and evergreen vegetation development in the central Mediterranean: a 5,500 year record from Lago Alimini Piccolo, Apulia, southeast Italy. *The Holocene* 19, 295–306.
- Di Rita, D., Magri, D., 2012. An overview of the Holocene vegetation history from the central Mediterranean coasts. *J. Mediterr. Earth Sci.* 4, 35–52.
- Di Rita, F., Anzidei, A.P., Magri, D., 2013. A Late glacial and early Holocene pollen record from Valle di Castiglione (Rome): vegetation dynamics and climate implications. *Quat. Int.* 288, 73–80.
- Drescher-Schneider, R., de Beaulieu, J.-L., Magny, M., Walter-Simonet, A.-V., Bossuet, G., Millet, L., Brugiapaglia, E.L., Drescher, A., 2007. Vegetation history, climate and human impact over the last 15 000 years at Lago dell'Accesa (Tuscany, Central Italy). *Veg. Hist. Archaeobot.* 16, 279–299.
- Dubois, J.M., 2001. Cycles climatiques et paramètres orbitaux vers 1 Ma. Etude de la Coupe de Monte San Giorgio (Caltagirone, Sicile): Palynologie, Isotope Stables, Calcimétrie. Mémoire DEA. Lyon University, Lyon, France.
- Farjon, A., 1998. World Checklist and Bibliography of Conifers. Royal Botanical Gardens, Kew, Richmond, U.K.
- Farjon, A., 2005. A Monograph of Cupressaceae and *Sciadopitys*. Royal Botanic Gardens, Kew, UK 1842460684.
- Fauquette, S., Bertini, A., 2003. Quantification of northern Italy Pliocene climate from pollen data: evidences for a very peculiar climate pattern. *Boreas* 32, 361–369.
- Fauquette, S., Comboureu-Nebout, N., 2013. Palaeoaltitude of the Sila Massif (Southern Apennines, Italy) and distribution of the vegetation belts at ca. 2.4 Ma (Early Pleistocene). *Rev. Palaeobot. Palynol.* 189, 1–7.
- Fauquette, S., Suc, J.-P., Guiot, J., Diniz, F., Feddi, N., Zheng, Z., Bessais, E., Drivalieri, A., 1999. Climate and biomes in the west Mediterranean area during the Pliocene. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 152, 15–36.
- Fauquette, S., Suc, J.-P., Bertini, A., Popescu, S.M., Warny, S., Bachiri-Taoufiq, N., Perez Villa, M., Chikhi, H., Subally, D., Feddi, N., Clauzon, G., Ferrier, J., 2006. How much did climate force the Messinian salinity crisis? Quantified climatic conditions from pollen records in the Mediterranean region. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 238, 281–301.
- Fauquette, S., Suc, J.-P., Jiménez-Moreno, G., Favre, E., Jost, A., Micheels, A., Bachiri-Taoufiq, N., Bertini, A., Clet-Pellerin, M., Diniz, F., Farjanel, G., Feddi, N., Zheng, Z., 2007. Latitudinal climatic gradients in Western European and Mediterranean regions from the Mid-Miocene (~15 Ma) to the Mid-Pliocene (~3.6 Ma) as quantified from pollen data. In: Williams, M., Haywood, A.M., Gregory, F.J., Schmidt, D.N. (Eds.), *Deep-time perspectives on climate change: marrying the signal from computer models and biological proxies*. The Micropalaeontological Society Special Publications. The Geological Society, London, pp. 481–502.
- Favaretto, S., Asioli, A., Miola, A., Piva, A., 2008. Preboreal climatic oscillations recorded by pollen and foraminifera in the Southern Adriatic Sea. *Quat. Int.* 190, 89–102.
- Federici, P.R., 1973. La tettonica recente dell'Appennino 1. Il bacino Villafranchiano di Sarzana e il suo significato nel quadro dei movimenti distensivi a nord-ovest delle Alpi Apuane. *Boll. Soc. Geol. Ital.* 92, 287–301.
- Ficcarelli, G., Abbazzi, L., Albanielli, A., Bertini, A., Coltorti, M., Magnatti, M., Masini, F., Mazza, P., Mezzabotta, C., Napoleone, G., Rook, L., Rustioni, M., Torre, D., 1997. Cesi an early Middle Pleistocene site in the Colfiorito basin (Umbro-Marchean Apennine), central Italy. *J. Quat. Sci.* 12, 507–518.
- Fletcher, W.J., Sánchez-Goni, M.F., Allen, J.R.M., Cheddadi, R., Comboureu-Nebout, N., Huntley, B., Lawson, I., Londeix, L., Magri, D., Margan, V., Muller, U.C., Naughton, F., Novenko, E., Roucoux, C., Tzedakis, P.C., 2010. Millennial-scale variability during the last glacial in vegetation records from Europe. *Quat. Sci. Rev.* 29, 2839–2864.
- Follieri, M., 1977. Evidence on the Plio-Pleistocene palaeofloristic evolution in central Italy. *Riv. Ital. Paleontol. Stratigr.* 83, 925–930.
- Follieri, M., Magri, D., Sadori, L., 1988. 250,000-year pollen record from Valle di Castiglione (Roma). *Pollen Spores* 30, 329–356.
- Follieri, M., Magri, D., Sadori, L., 1989. Pollen stratigraphical synthesis from Valle di Castiglione (Roma). *Quat. Int.* 3 (4), 81–84.
- Follieri, M., Giardini, M., Magri, D., Sadori, L., 1998. Palynostratigraphy of the last glacial period in the volcanic region of Central Italy. *Quat. Int.* 47 (48), 3–20.
- Francavilla, F., Bertolani-Marchetti, D., Tomadin, L., 1970. Ricerche stratigrafiche, sedimentologiche e palinologiche sul Villafranchiano tipo. *Giorn. Geol.* 36 (02), 701–741.
- Fusco, F., 1996. Analisi polliniche nelle successioni pleistoceniche inferiori della Valle del Lamone (Appennino nord-orientale). Evoluzione paleovegetazionale e paleoclimatica. Unpublished PhD Thesis, University of Bologna, Italy, 96 pp.
- Fusco, F., 2007. Vegetation response to early Pleistocene climatic cycles in the Lamone valley (Northern Apennines, Italy). *Rev. Palaeobot. Palynol.* 145, 1–23.
- Fusco, F., 2010. *Picea* + *Tsuga* pollen record as a mirror of oxygen isotope signal? An insight into the Italian long pollen series from Pliocene to Early Pleistocene. *Quat. Int.* 225, 58–74.
- Ge.Mi.Na. (Ed.), 1962. *Ligniti e Torbe dell'Italia Continentale*. Società Geomineraria Nazionale, ILTE Ed., Roma, Italy (319 pp.).
- Ghinassi, M., Magi, M., Sagri, M., Singer, B.S., 2004. Arid climate 2.5 Ma in the Plio-Pleistocene Valdarno Basin (Northern Apennines, Italy). *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 207, 37–57.
- Giorgi, F., 2006. Climate change hot-spots. *Geophys. Res. Lett.* 33, L08707.
- Giunta, S., Negri, A., Morigi, C., Capotondi, L., Comboureu-Nebout, N., Emeis, K.C., Sangiorgi, F., Vigliotti, L., 2003. Colcolithophorid ecostratigraphy and multi-proxy paleoceanographic reconstruction in the Southern Adriatic Sea during the last deglacial time (Core AD91–17). *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 190, 39–59.
- Grieser, J., Gommers, R., Bernardi, M., 2006. New LocClim — the Local Climate Estimator of FAO. European Geosciences Union 2006, *Geophys. Res. Abstr.* 8, 08305 (Software available for download at http://www.fao.org/nr/climpag/pub/en3_051002_en.asp).
- Grüger, E., 1975. Pollenanalyse spätpleistozäner und holozäner sedimente aus der Adria. *Geol. Jahrb.* A29, 3–32.
- Grüger, E., 1977. Pollenanalytische Untersuchung zur wurm-zeitlichen Vegetationsgeschichte von Kalabrien (Suditalien). *Flora* 166, 475–489.
- Guerrera, F., Coccioni, D., Corradini, D., Bertoldi, R., 1984. Caratteristiche litosedimentologiche e micropaleontologiche (Foraminiferi, Dinoflagellati, pollini e spore) di successioni "tripolacee" plioceniche del bacino di Caltanisetta. *Boll. Soc. Geol. Ital.* 103, 629–660.
- Guiot, J., 1990. Methodology of the last climatic cycle reconstruction in France from pollen data. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 80, 49–69.
- Hilgen, F.J., 1987. Sedimentary rhythms and high-resolution chronostratigraphic correlations in the Mediterranean Pliocene. *Newsl. Stratigr.* 17, 109–127.
- Hilgen, F.J., Langeris, C.G., 1988. The age of the Miocene-Pliocene boundary in the Capo Rossello area (Sicily). *Earth Planet. Sci. Lett.* 91, 214–222.
- Howell, M.W., Thunell, R., Tappa, E., Rio, D., Sprovieri, R., 1988. Late Neogene laminated and opal-rich facies from the Mediterranean region: geochemical evidence for mechanisms of formation. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 64, 265–286.
- IPCC, 2007. *Climate Change 2007: Synthesis Report*. Contribution of Working Groups I, II and III to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change (Geneva, Switzerland, 104 pp.).
- Jalut, G., Esteban Amat, A., Bonnet, L., Gauquelin, T., Fontugne, M., 2000. Holocene climatic changes in the Western Mediterranean, from south-east France to south-east Spain. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 160, 255–290.
- Jalut, G., Dedoubat, J.-J., Fontugne, M., Otto, T., 2009. Holocene circum-Mediterranean vegetation changes: climate forcing and human impact. *Quat. Int.* 200, 4–18.

- Joannin, S., Quillévéré, F., Suc, J.P., Lécuyer, C., Martineau, F., 2007. Early Pleistocene climate changes in the central Mediterranean region as inferred from integrated pollen and foraminiferal stable isotope analyses. *Quat. Res.* 67, 264–274.
- Joannin, S., Ciaranfi, N., Stefanelli, S., 2008. Vegetation changes during the late early Pleistocene at Montalbano Jonico (Province of Matera, southern Italy) based on pollen analysis. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 270, 92–101.
- Joannin, S., Bassinot, F., Combourieu-Nebout, N., Peyron, O., Beaudouin, C., 2011. Vegetation response to obliquity and precession forcing during the Mid-Pleistocene transition in Western Mediterranean region (ODP site 976). *Quat. Sci. Rev.* 30, 280–297.
- Joannin, S., Brugiapaglia, E., de Beaulieu, J.L., Bernado, L., Magny, M., Peyron, O., Goring, S., Vanniere, B., 2012. Pollen-based reconstruction of Holocene vegetation and climate in southern Italy: the case of Lago di Trifoglietti. *Clim. Past* 8, 1973–1996.
- Joannin, S., Vanniere, B., Galop, D., Peyron, O., Haas, J.N., Gilli, A., Chapron, E., Wirth, S., Anselmetti, F., Desmet, M., Magny, M., 2013. Climate and vegetation changes during the Lateglacial and Early–Mid Holocene in Lake Ledro (Southern Alps, Italy). *Clim. Past* 9, 913–933.
- Joannin, S., Magny, M., Peyron, O., Vanniere, B., Galop, D., 2014. Climate and land-use changes during the four last millennia in Southern Alps as recorded at Lake Ledro (Italy). *The Holocene* 24, 591–602.
- Kent, D.V., Rio, D., Massari, F., Kukla, G., Lanci, L., 2002. Emergence of Venice during the Pleistocene. *Quat. Sci. Rev.* 21, 1719–1727.
- Klotz, S., 1999. Neue Methoden der Klimarekonstruktion-angewendet auf quartäre Pollensequenzen der französischen Alpen. *Tüb. Mikropaläontologische Mitt.* 2 (169 pp.).
- Klotz, S., Fauquette, S., Combourieu-Nebout, N., Uhl, D., Suc, J.P., Mosbrugger, V., 2006. Seasonality intensification and long-term winter cooling as a part of the Late Pliocene climate development. *Earth Planet. Sci. Lett.* 241, 174–187.
- Lebreton, V., 2002. Végétation et climat au Pléistocène inférieur et moyen à La Pineta (Isernia, Italie). *C. R. Palevol* 1, 11–17.
- Leroy, S., 2007. Progress in palynology of the Gelasian–Calabrian stages in Europe: ten messages. *Rev. Micropaleontol.* 50, 293–308.
- Leroy, S., Giral, S., Francus, P., Seret, G., 1996. The high sensitivity of the palynological record in the Vico maar lacustrine sequence (Latium, Italy) highlights the climatic gradient through Europe for the last 90 ka. *Quat. Sci. Rev.* 15, 189–201.
- Lionello, P., Malanotte-Rizzoli, P., Boscolo, R., Alpert, P., Artale, V., Li, L., Luterbacher, J., May, W., Trigo, R., Tsimplis, M., Ulbrich, U., Xoplaki, E., 2006. The Mediterranean climate: an overview of the main characteristics and issues. In: Lionello, P., Malanotte-Rizzoli, P., Boscolo, R. (Eds.), *Mediterranean Climate Variability and Predictability*. Elsevier, Amsterdam, pp. 1–26.
- Lisiecki, L.E., Raymo, M.E., 2005. A Pliocene–Pleistocene stack of 57 globally distributed benthic $\delta^{18}\text{O}$ records. *Paleoceanography* 20, PA1003. <http://dx.doi.org/10.1029/2004PA001071>.
- Lona, F., 1950. Contributi alla storia della vegetazione e del clima nella Val Padana e Analisi pollinica del giacimento villafranchiano di Lefte (Bergamo). *Atti Soc. Ital. Sci. Nat.* 89, 123–178.
- Lona, F., 1962. Prime analisi pollinologiche sui depositi terziari e quaternari di Castell'Arquato: reperti di vegetazione da clima freddo sotto le formazioni calcaree a *Amphistegina*. *Boll. Soc. Geol. Ital.* 81, 1–5.
- Lona, F., Bertoldi, R., 1972. La storia del Plio–Pleistocene italiano in alcune sequenze vegetazionali lacustri e marine. *Atti Accad. Naz. Lincei* 11, 1–45.
- Lona, F., Follieri, M., 1957. Successione pollinica della serie superiore (Günz–Mindel) di Lefte (Bergamo). *Veröff. Geobot. Inst. Rübel Zür.* 34, 86–98.
- Lona, F., Ricciardi, E., 1961a. Studio pollinologico stratigrafico su una serie lacustre pleistocenica dell'Italia centrale (Bacino di Gubbio, Perugia). *Pollen Spores* 3, 93–100.
- Lona, F., Ricciardi, E., 1961b. Reperti pollinologici nei depositi pleistocenici del bacino lacustre del Mercure (Italia meridionale, Regione Lucano-Calabria). *Pollen Spores* 3 (1), 85–92.
- Lourens, L., Antonarakou, F., Hilgen, F.J., Van Hoof, A.M., Vergnaud-Grazzini, C., Zacharias, W.J., 1996. Evaluation of the Plio–Pleistocene astronomical timescale. *Paleoceanography* 11, 491–493.
- Lourens, L.J., Hilgen, F.J., Laskar, J., Shackleton, N.J., Wilson, D., 2004. The Neogene Period. In: Gradstein, F.M., Ogg, J.G., Smith, A.G. (Eds.), *A Geologic Time Scale 2004*. Cambridge University Press, pp. 409–440.
- Magri, D., 1999. Late-Quaternary vegetation history at Lagaccione near Lago di Bolsena (central Italy). *Rev. Palaeobot. Palynol.* 106, 171–208.
- Magri, D., 2010. Persistence of tree taxa in Europe and Quaternary climate changes. *Quat. Int.* 219, 145–151.
- Magri, D., Palombo, M.R., 2013. Early to Middle Pleistocene dynamics of plant and mammal communities in South West Europe. *Quat. Int.* 288, 63–72.
- Magri, D., Sadori, L., 1999. Late Pleistocene and Holocene pollen stratigraphy at Lago di Vico (central Italy). *Veg. Hist. Archaeobot.* 8, 247–260.
- Magri, D., Di Rita, F., Palombo, M.R., 2010. An early Pleistocene interglacial record from an intermontane basin of central Italy (Scoppito, L'Aquila). *Quat. Int.* 225, 106–113.
- Mai, D.H., 1994. Fossile Koniferenreste in der meridionalen Zone Europas. *Feddes Repert.* 105, 207–227.
- Mai, D.H., 1995. Paleocarpological investigations in the Villafranchian (Pliocene) of Italy. *Boll. Mus. Reg. Sci. Nat. Torino* 13, 407–437.
- Martinetto, E., 2009. Palaeoenvironmental significance of plant macrofossils from the Pianico Formation, Middle Pleistocene of Lombardy, North Italy. *Quat. Int.* 204, 20–30.
- Martinetto, E., Vassio, E., 2010. Reconstructing “Plant Community Scenarios” by means of palaeocarpological data from the CENOFITA database, with an example from the Ca' Viettone site (Pliocene, Northern Italy). *Quat. Int.* 225 (1), 25–36.
- Martinetto, E., Scardia, G., Varrone, D., 2007. Magnetobiostratigraphy of the Stura di Lanzo fossil forest succession (Piedmont, Italy). *Riv. Ital. Paleontol. Stratigr.* 113 (1), 109–125.
- Martinetto, E., Bertini, A., Basili, G., Baldanza, A., Bizzarri, R., Cherin, M., Gentili, S., Pontini, M.R., 2014. The plant record of the Dunarobba and Pietrafitta sites in the Plio–Pleistocene palaeoenvironmental context of central Italy. *Alp. Mediterr. Quat.* 27 (1), 29–72.
- Martinetto, E., Monegato, G., Irace, A., Vaiani, S.C., Vassio, E., 2015. Pliocene and Early Pleistocene carpological records of terrestrial plants from the southern border of the Po Plain (northern Italy). *Rev. Palaeobot. Palynol.* 218, 148–166.
- Massari, F., Rio, D., Sgavetti, M., Prosser, G., D'Alessandro, A., Asioli, A., Capraro, L., Fornaciari, E., Tateo, F., 2002. Interplay between tectonics and glacio-eustasy: Pleistocene succession of the Crotona Basin, Calabria (southern Italy). *Geol. Soc. Am. Bull.* 114, 1183–1209.
- Massari, F., Rio, D., Serandrei Barbero, R., Asioli, A., Capraro, L., Fornaciari, E., Vergerio, P.P., 2004. The environment of Venice area in the past two million years. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 202, 273–308.
- Médail, F., Quézel, P., 1997. Hot-spots analysis for conservation of plant biodiversity in the Mediterranean Basin. *Ann. Mo. Bot. Gard.* 84, 112–127.
- Médail, F., Quézel, P., 1999. Biodiversity hotspots in the Mediterranean Basin: setting global conservation priorities. *Conserv. Biol.* 13, 1510–1513.
- Mercuri, A.M., Bandini Mazzanti, M., Torri, P., Vigliotti, L., Bosi, G., Florenzano, A., Olmi, L., Massamba N'siala, I., 2012. Marine/terrestrial integration for mid-late Holocene vegetation history and the development of the cultural landscape in the Po Valley as a result of human impact and climate change. *Veg. Hist. Archaeobot.* 21, 353–372.
- Mercuri, A.M., Bandini Mazzanti, M., Florenzano, A., Montecchi, M.C., Rattighieri, E., 2013. *Olea, Juglans and Castanea*: the OJC group as pollen evidence of the development of human-induced environments in the Italian peninsula. *Quat. Int.* 303, 24–42.
- Monegatti, P., Raffi, S., Raineri, G., 1997. The Monte Falcone–Rio Riorzo composite section: biostratigraphic and ecobiostratigraphic remarks. *Boll. Soc. Paleontol. Ital.* 36, 245–260.
- Monegatti, P., Canali, G., Bertoldi, R., Albanielli, A., 2002. The classical late Piacenzian Monte Falcone–Rio Crevallese section (Northern Italy): palynological evidence and biomagnetostratigraphic constraints for climatic cyclicity and local mollusc extinctions. *Geobios Mem. Spéc.* 24, 219–227.
- Moscariello, A., Ravazzi, C., Brauer, A., Mangili, C., Chiesa, S., Rossi, S., de Beaulieu, J.L., Reille, M., 2000. A long lacustrine record from the Pianico–Sèllere basin (Middle–Late Pleistocene, northern Italy). *Quat. Int.* 73 (74), 47–68.
- Mullenders, W., Faverio, V., Coremans, M., Dirckx, M., 1996. Analyses polliniques de sondages à Venise (VE-I, VE-I bis, VE-II). *Aardk. Meded.* 7, 87–116.
- Munno, R., Petrosino, P., Romano, P., Russo Ermolli, E., Juviné, E., 2001. A Late Middle Pleistocene climatic cycle in southern Italy inferred from pollen analysis and tephrostratigraphy of the Acerno lacustrine succession. *Géog. Phys. Quatern.* 55, 87–99.
- Muttoni, G., Carcano, C., Garzanti, E., Ghielmi, M., Piccin, A., Pini, R., Rogledi, S., Sciuinich, D., 2003. Onset of major Pleistocene glaciations in the Alps. *Geology* 31, 989–992.
- Muttoni, G., Ravazzi, C., Breda, M., Pini, R., Laj, C., Kissel, C., Mazaud, A., Garzanti, E., 2007. Magnetostratigraphic dating of an intensification of glacial activity in the southern Italian Alps during Marine Isotope Stage 22. *Quat. Res.* 67, 161–173.
- Napoleone, G., Albanielli, A., Azzaroli, A., Bertini, A., Magi, M., Mazzini, M., 2003. Calibration of the upper Valdarno basin to the Plio–Pleistocene for correlating the Apennine continental sequences. *Il Quaternario* 16, 131–166.
- Narcisi, B., Anselmi, B., 1998. Sedimentological investigations on a Late-Quaternary core from the Lagaccione maar (central Italy): palaeoclimatic and palaeoenvironmental inferences. *Quat. Int.* 47–48, 21–28.
- Narcisi, B., Anselmi, B., Catalano, F., Dai Pra, G., Magri, G., 1992. Lithostratigraphy of the 250,000 year record of lacustrine sediments from the Valle di Castiglione Crater, Roma. *Quat. Sci. Rev.* 11, 353–362.
- Oldfield, F., Asioli, A., Accorsi, C.A., Mercuri, A.M., Juggins, S., Langone, L., Rolph, T., Trincardi, F., Wolff, G., Gibbs, Z., Vigliotti, L., Frignani, M., van der Post, K., Branch, N., 2003. A high resolution late Holocene palaeoenvironmental record from the central Adriatic Sea. *Quat. Sci. Rev.* 22 (2–4), 319–342.
- Orain, R., Lebreton, V., Russo Ermolli, E., Combourieu-Nebout, N., Sémah, A.-M., 2013. *Carya* as marker for tree refuges in southern Italy (Boiano basin) at the Middle Pleistocene. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 369, 295–302.
- Ozenda, P., 1975. Sur les étages de végétation dans les montagnes du bassin méditerranéen. *Doc. Cartogr. Ecol.* 16, 1–32.
- Ozenda, P., 1994. La végétation du continent européen. Delachaux and Niestlé eds, 280 pp.
- Petrosino, P., Jicha, B.R., Mazzeo, F.C., Russo Ermolli, E., 2014a. A high resolution tephrochronological record of MIS 14–12 in the Southern Apennines (Acerno basin, Italy). *J. Volcanol. Geotherm. Res.* 274, 34–50.
- Petrosino, P., Russo Ermolli, E., Donato, P., Jicha, B., Robustelli, G., Sardella, R., 2014b. Using tephrochronology and palynology to date to the MIS 13 lacustrine sediments of the Mercure Basin (Southern Apennine – Italy). *Ital. J. Geosci.* <http://dx.doi.org/10.3301/IJG.2013.22>.
- Peyron, O., Guiot, J., Cheddadi, R., Tarasov, P., Reille, M., de Beaulieu, J.L., Bottema, S., Andrieu, V., 1998. Climatic reconstruction in Europe for 18,000 yr B.P. from pollen data. *Quat. Res.* 49, 183–196.
- Peyron, O., Goring, S., Dormoy, I., Kotthoff, U., Pross, J., de Beaulieu, J.L., Drescher-Schneider, R., Vanniere, B., Magny, M., 2011. Holocene seasonality changes in central Mediterranean reconstructed from Lake Accesa and Tenaghi Philippon pollen sequences. *The Holocene* 21, 131–146.
- Peyron, O., Magny, M., Goring, S., Joannin, S., de Beaulieu, J.L., Brugiapaglia, E., Sadori, L., Garfi, G., Kouli, K., Ioakim, C., Combourieu-Nebout, N., 2013. Contrasting patterns of climatic changes during the Holocene across the Italian Peninsula reconstructed from pollen data. *Clim. Past* 9, 1233–1252.
- Pignatti, S., 1998. I boschi d'Italia. *Sinecologia e biodiversità*. UTET, Torino, Italy (XVI + 677 pp.).

- Pignatti, G., 2011. La vegetazione forestale di fronte ad alcuni scenari di cambiamento climatico in Italia. *Forest* 8, 1–12.
- Pini, R., Ravazzi, C., Donegana, M., 2009a. Pollen stratigraphy, vegetation and climate history of the last 215 ka in the Azzano Decimo core (plain of Friuli, north-eastern Italy). *Quat. Sci. Rev.* 28, 1268–1290.
- Pini, R., Ravazzi, C., Monegato, G., 2009b. La storia vegetazionale e climatica del Pleistocene Superiore nella successione lacustre continua di Fimon (Colli Berici, Vicenza) Convegno AIQUA. “La variabilità del clima nel Quaternario: la ricerca italiana” 18–20, 76–77 (Roma).
- Pinti, D.L., Quidelleur, X., Chiesa, S., Ravazzi, C., Gillot, P.Y., 2001. K–Ar dating of an early Middle Pleistocene distal tephra in the interglacial varved succession of Piànico–Sèllere (Southern Alps, Italy). *Earth Planet. Sci. Lett.* 188, 1–7.
- Piva, A., Ascoli, A., Trincardi, F., Schneider, R.R., Vigliotti, L., 2008. Late-Holocene climate variability in the Adriatic Sea (Central Mediterranean). *The Holocene* 18 (1), 153–167.
- Pons, A., Quézel, P., 1985. The history of the flora and vegetation and past and present human disturbance in the Mediterranean region. In: Gomez-Campo, C. (Ed.), *Plant Conservation in the Mediterranean Area*. W. Junk, Dordrecht, Pays-Bas.
- Pons, A., Suc, J.P., Reille, M., Combourieu Nebout, N., 1995. The history of dryness in regions with a Mediterranean climate. In: Roy, J., Aronson, J., di Castri, F. (Eds.), *Time Scales of Biological Responses to Water Constraints*. Acad. Publishing bv, Amsterdam, pp. 169–188.
- Pontini, M.R., 1997. Analisi Palinologica e Interpretazione Paleoclimatica dei Depositi Continentali del Bacino Tiberino (Umbria, Italia). Unpublished Ph.D Thesis, University of Perugia, Italy, 134 pp.
- Pontini, M.R., Bertini, A., 2000. Late Pliocene vegetation and climate in central Italy: high resolution pollen analysis from the Fosso Bianco section (Tiberino Basin). *Geobios* 33, 519–526.
- Pontini, M.R., Albanelli, A., Basilici, G., Bertini, A., Napoleone, G., 2002. Pollen record and magnetostratigraphy of the Middle–Late Pliocene lacustrine sequence in the Tiberino basin, (central Italy). *Boll. Soc. Geol. Ital.* 1, 467–472.
- Poore, R.Z., Berggren, W.A., 1975. The morphology and classification of *Neoglobobulimina atlantica* (Berggren). *J. Foraminif. Res.* 5 (2), 76–84.
- Quézel, P., Médail, F., 2003. *Ecologie et biogéographie des forêts du bassin méditerranéen*, Elsevier-Lavoisier eds, Paris, France, 571 pp.
- Raffi, I., Rio, D., 1980. Nuove osservazioni sulla distribuzione del nannoplancton calcareo nella serie di Le Castella (Calabria). *Paleontologia Stratigrafica ed Evoluzione* Quaderno 1 pp. 181–186.
- Ravazzi, C., 1993. Variazioni Ambientali e Climatiche al Margine Meridionale Delle Alpi nel Pleistocene Inferiore: Stratigrafia e Analisi Pollinica della Serie di Leffe. (PhD Thesis). University of Milan, Italy.
- Ravazzi, C., 2002. Late Quaternary history of spruce in southern Europe. *Rev. Palaeobot. Palynol.* 120, 131–177.
- Ravazzi, C., 2003. Gli Antichi Bacini Lacustri e i Fossili di Leffe, Ranica e Piànico–Sèllere. CNR Special Publications. Quaderni di Geodinamica Alpina e Quaternaria, Bergamo, Italy (176 pp.).
- Ravazzi, C., Moscarello, A., 1998. Sedimentation, palaeoenvironmental evolution and time duration of earliest Pleistocene climatic cycles in the 24–56 m FM core interval (Leffe basin, Northern Italy). In: van Kolfschoten, Th., Gibbard, P. (Eds.), *Proceedings of the INQUA–SEQS Symposium “The dawn of the Quaternary”* Meded. Ned. Inst. Toegep. Geowet. TNO 60, 467–490.
- Ravazzi, C., Rossignol-Strick, M., 1994. Interglacial–glacial cycles on the Early Pleistocene of the Leffe basin (northern Italy): preliminary report. *Hist. Biol.* 9, 11–15.
- Ravazzi, C., Rossignol-Strick, M., 1995. Vegetation change in a climatic cycle of early Pleistocene age in the Leffe basin (Northern Italy). *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 117, 105–122.
- Ravazzi, C., Pini, R., Breda, M., Martinetto, E., Muttoni, G., Chiesa, S., Confortini, F., Egli, R., 2005. The lacustrine deposits of Fornaci di Ranica (late Early Pleistocene, Italian Pre-Alps): stratigraphy, palaeoenvironment and geological evolution. *Quat. Int.* 131, 35–58.
- Ravazzi, C., Pini, R., Breda, M., 2009. Reconstructing the palaeoenvironments of the early Pleistocene mammal faunas from the pollen preserved on fossil bones. *Quat. Sci. Rev.* 28, 2940–2954.
- Ricciardi, E., 1961. Analisi pollinologica dei sedimenti lacustri lignitiferi di Pietrafitta (Perugia, Italia). *Pollen Spores* 3 (2), 325–328.
- Ricciardi, E., 1965. Analisi polliniche di una serie stratigrafica dei sedimenti lacustri del Pleistocene Inferiore nel Bacino di Leonessa (Rieti–Italia Centrale). *G. Bot. Ital.* 72, 62–82.
- Rio, D., 1982. The fossil distribution of Cocolithophore Genus *Gephyrocapsa* Kamptner and related Plio–Pleistocene chronostratigraphic problems. In: Prell, W.L., Gardner, J.V., et al. (Eds.), *Initial Rep. Deep Sea Drill. Proj.* 68, 325–343.
- Rio, D., Thunell, R., Sprovieri, R., Bukry, D., Di Stefano, E., Howell, M., Raffi, I., Sancetta, C., San Filippo, A., 1989. Stratigraphy and depositional history of the Pliocene Bianco section, Calabria, southern Italy. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 76, 85–105.
- Rio, D., Channell, J.E.T., Bertoldi, R., Poli, M.S., Vergerio, P.P., Raffi, I., Sprovieri, R., Thunell, R.C., 1997. Pliocene sapropels in the northern Adriatic area: chronology and palaeoenvironmental significance. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 135, 1–25.
- Robustelli, G., Russo Ermolli, E., Petrosino, P., Jicha, B., Sardella, R., Donato, P., 2014. Tectonic and climatic control on geomorphological and sedimentary evolution of the Mercure basin, southern Apennines, Italy. *Geomorphology* 214, 423–435.
- Rossi, S., 2003. Etude pollinique de la sequence lacustre Pléistocène de Piànico–Sèllere (Italie). (PhD thesis). Université de Droit, d'Economie et des Sciences d'Aix Marseille III.
- Rossignol-Strick, M., Planchais, N., 1989. Climate patterns revealed by pollen and oxygen isotope records of a Tyrrhenian Sea core. *Nature* 342, 413–416.
- Rossignol-Strick, M., Planchais, N., Paterne, M., Duzert, D., 1992. Vegetation dynamics and climate during the last deglaciation in the South Adriatic basin from a marine record. *Quat. Sci. Rev.* 11, 415–423.
- Roulleau, E., Pinti, D., Rouchonb, V., Quidelleur, X., Gillot, P.Y., 2009. Tephro-chronostratigraphy of the lacustrine interglacial record of Piànico, Italian Southern Alps: identifying the volcanic sources using radiogenic isotopes and trace elements. *Quat. Int.* 204, 31–43.
- Russo Ermolli, E., 1994. Analyse pollinique de la succession lacustre pléistocène du Vallo di Diano (Campanie, Italie). *Ann. Soc. Géol. Belg.* 117, 333–354.
- Russo Ermolli, E., 1999. Vegetation dynamics and climate changes at Camerota (Campania, Italy) at the Pliocene–Pleistocene boundary. *II Quaternario* 12, 207–214.
- Russo Ermolli, E., 2000. Pollen analysis of the Acerno palaeolacustrine succession (Middle Pleistocene, southern Italy). *Geol. Soc. Lond. Spec. Publ.* 181, 151–159.
- Russo Ermolli, E., Cheddadi, R., 1997. Climatic reconstruction during the middle Pleistocene: a pollen record from Vallo di Diano (southern Italy). *Geobios* 30 (6), 735–744.
- Russo Ermolli, E., Juvigné, E., Bernasconi, S., Brancaccio, L., Cinque, A., Lirer, L., Ozer, A., Santangelo, N., 1995. Le premier stratotype continental de quatre stades isotopiques successifs du Pléistocène moyen pour le bassin méditerranéen septentrional: le Vallo di Diano (Campanie, Italie). *C. R. Acad. Sci. Paris* 321, 877–884.
- Russo Ermolli, E., Aucelli, P.P.C., Di Rollo, A., Mattei, M., Petrosino, P., Porreca, M., Rosskopf, C.M., 2010a. An integrated stratigraphical approach to the Middle Pleistocene succession of the Sessano basin (Molise, Italy). *Quat. Int.* 225, 114–127.
- Russo Ermolli, E., Sardella, R., Di Maio, G., Petronio, C., Santangelo, N., 2010b. Pollen and mammals from the late Early Pleistocene site of Saticula (Sant’Agata de’ Goti, Benevento, Italy). *Quat. Int.* 225, 128–137.
- Russo-Ermolli, E., di Pasquale, G., 2002. Vegetation dynamics of southwestern Italy in the last 20,000 yr inferred from pollen analysis of a Tyrrhenian Sea core. *Veg. Hist. Archaeobot.* 11 (3), 211–220.
- Sabato, L., Bertini, A., Masini, F., Albanelli, A., Napoleone, G., Pieri, P., 2005. The lower and middle Pleistocene geological record of the San Lorenzo lacustrine sequence in Sant’Arcangelo basin. (Southern Apennines, Italy). *Quat. Int.* 131, 59–69.
- Sachse, M., 2001. Oleaceous laurophyllous leaf fossils and pollen from the European Tertiary. *Rev. Palaeobot. Palynol.* 115, 213–234.
- Sadori, L., Narcisi, B., 2001. The Postglacial record of environmental history from Lago di Pergusa, Sicily. *The Holocene* 11, 655–671.
- Sadori, L., Giraudi, C., Petitti, P., Ramrath, A., 2004. Human impact at Lago di Mezzano (central Italy) during the Bronze Age: a multidisciplinary approach. *Quat. Int.* 113, 5–17.
- Sadori, L., Giardini, M., Chiarini, E., Mattei, M., Papasodaro, F., Porreca, M., 2010. Pollen and macrofossil analyses of Pliocene lacustrine sediments (Salto river valley, central Italy). *Quat. Int.* 225, 44–57.
- Sadori, L., Jahns, S., Peyron, O., 2011. Mid-Holocene vegetation history of the central Mediterranean. *The Holocene* 21, 117–129.
- Sadori, L., Bertini, A., Combourieu-Nebout, N., Kouli, K., Mariotti Lippi, M., Roberts, N., Mercuri, A.M., 2013a. Palynology and Mediterranean vegetation history. *Flora Mediterr.* 23, 141–156.
- Sadori, L., Ortu, E., Peyron, O., Zanchetta, G., Vannière, B., Desmet, M., Magny, M., 2013b. The last 7 millennia of vegetation and climate changes at Lago di Pergusa (central Sicily, Italy). *Clim. Past* 9, 1969–1984.
- Sánchez Goni, M.F., Cacho, I., Turon, J.L., Guiot, J., Sierro, F.J., Peyrouquet, J.P., Grimalt, J.O., Shackleton, N.J., 2002. Synchronicity between marine and terrestrial responses to millennial scale climatic variability during the last glacial period in the Mediterranean region. *Clim. Dyn.* 19, 95–105.
- Sangiorgi, L., Capotondi, L., Combourieu-Nebout, N., Vigliotti, F., Brinkhuis, H., Giunta, S., Lotter, A.F., Morigi, C., Negri, A., Reichert, G.J., 2003. Holocene seasonal sea surface temperature variations in the South Adriatic Sea inferred from a multi-proxy approach. *J. Quat. Sci.* 18, 723–732.
- Schneider, R., 1985. Analyse palynologique dans l’Aspromonte en Calabre (Italie Meridionale). *Cah. Lignes Prehist. Protohist.* 2, 279–288.
- Sprovieri, R., Sprovieri, M., Caruso, A., Pelosi, N., Bonomo, S., Ferraro, L., 2006. Astronomic forcing on the planktonic foraminifera assemblage in the Piacenzian Punta Piccola section (southern Italy). *Paleoceanography* 21, PA4204. <http://dx.doi.org/10.1029/2006PA001268>.
- Suc, J.P., 1984. Origin and evolution, of the Mediterranean vegetation and climate in Europe. *Nature* 307, 429–432.
- Suc, J.P., Bessais, E., 1990. Pérennité d’un climat thermo-xérique en Sicile avant, pendant, après la crise de salinité messinienne. *C. R. Acad. Sci. Paris* 294, 1003–1008.
- Suc, J.P., Bertini, A., Combourieu-Nebout, N., Diniz, F., Leroy, S., Russo Ermolli, E., Zheng, Z., Bessais, E., Ferrier, J., 1995. Structure of west Mediterranean and climate since 5.3 Ma. *Acta Zool. Cracov.* 38, 3–16.
- Tomaselli, R., Baldazzi, A., Filippello, S., 1973. Carta Bioclimatica d’Italia. La vegetazione forestale d’Italia. Ministero Agricoltura e Foreste, Roma, pp. 5–24.
- Tzedakis, P.C., 2005. Towards an understanding of the response of southern European vegetation to orbital and suborbital climate variability. *Quat. Sci. Rev.* 25, 1585–1599.
- Tzedakis, P.C., 2007. Seven ambiguities in the Mediterranean palaeoenvironmental narrative. *Quat. Sci. Rev.* 26, 2042–2066.
- Tzedakis, P.C., Channell, J.E.T., Hodell, D.A., Kleiven, H.F., Skinner, L.C., 2012. Determining the natural length of the current interglacial. *Nat. Geosci.* 5, 138–141.
- Urban, B., Arias, C., Bigazzi, G., Bonadonna, F., 1983. Early Pleistocene palynostratigraphy of Fornace Tini, Valle Ricca (Central Italy). *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 41, 153–164.
- Vai, G.B., 1988. A field trip guide to the Romagna Apennine geology. The Lamone valley. In: De Giuli, C., Vai, G.B. (Eds.), *Fossil Vertebrates in the Lamone valley, Romagna Apennines*, International Workshop: Continental Faunas at the Mio-Pliocene Boundary, Faenza, March 28–31, 1988, Guidebook, pp. 7–37.
- Vaiani, S.C., Venezia, P., 1999. La sezione pleistocenica del Lamone (Appennino Romagnolo): associazioni a foraminiferi ed evoluzione paleoambientale. *Boll. Soc. Paleontol. Ital.* 38, 39–57.

- Valleri, G., Bertoldi, R., Bertini, A., 1990. Foraminifer and pollen assemblages from the Pliocene of Ponte an Elsa (Valdarno inferiore, Tuscany). *Boll. Soc. Paleontol. Ital.* 29, 321–333.
- van Otterloo, R.H., Sevink, J., 1983. The Quaternary Evolution of the Upper Volturno Basin. In: Isernia la Pineta (Ed.), Calderini, Bologna, pp. 35–39.
- Venetier, M., Ripert, C., Maille, E., Blanc, L., Torre, F., Roche, P., Tatoni, T., Brun, J.-J., 2010. A new bioclimatic model calibrated with vegetation for Mediterranean forest areas. *Ann. For. Sci.* 65, 711–724.
- von Koenigswald, W., Kolfschoffen, T., 1996. The *Mymomys arvicola* boundary and the enamel thickness quotient (SDQ) of *Arvicola* as stratigraphic markers in the Middle Pleistocene. In: Turner, C. (Ed.), *The Early Middle Pleistocene in Europe*. Balkema, Rotterdam, pp. 211–226.
- Wang, C.W., 1961. *The forest of China with a survey of grassland and desert vegetation*. Maria Moors Cabot Foundation Publications Series 5. Harvard University, Cambridge, UK.
- Wang, F.H., 1986. On the systematic of *Cathaya*. Coll. Fondation Emberger- CH Sauvage. L'évolution des Gymnospermes, approche biologique et paléobiologique. Abstract volume 54–55.
- Watts, W.A., Allen, J.R.M., Huntley, B., 1996. Vegetation history and palaeoclimate of the Last Glacial Period at Lago Grande di Monticchio, southern Italy. *Quat. Sci. Rev.* 15, 113–132.
- Watts, W.A., Allen, J.R.M., Huntley, B., 2000. Palaeoecology of three interstadial events during oxygen-isotope Stages 3 and 4: a lacustrine record from Lago Grande di Monticchio, southern Italy. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 155, 83–93.
- Zheng, Z., 1990. Végétations et climats néogènes des Alpes maritimes franco-italiennes d'après les données de l'analyse palynologique. *Paléobiol. Cont.* 17, 217–244.
- Zheng, Z., Cravatte, J., 1986. Etude palynologique du Pliocène de la Côte d'Azur (France) et du littoral Ligure (Italie). *Geobios* 9 (6), 815–823.
- Zonneveld, K.A.F., 1996. Palaeoclimatic reconstruction of the last deglaciation (18 ka. BP. – 8 ka. BP.) in the Adriatic Sea region: a land-sea correlation based on palynological evidence. *Palaeogeogr. Palaeoclimatol. Palaeoecol.* 122, 89–106.